


**PRELIMINARY ASSESSMENT  
ACME BRICK STRIP MINES  
COLLINSVILLE, OKLAHOMA, TULSA COUNTY**

**November 16, 1992**

**OKLAHOMA STATE DEPARTMENT OF HEALTH**

**Prepared By:**

**David S. Crow, Environmental Specialist**

A handwritten signature in black ink, appearing to read 'David S. Crow', written in a cursive style.

**Reviewed and Approved By:**

A handwritten signature in black ink, appearing to read 'Richard L. Brooks, Sr.', written in a cursive style.

**Richard L. Brooks, Sr. Environmental Specialist**

## Table of Contents

Topic	Pages
I. Introduction	3
II. Site Characteristic, Operational History, and Waste Characteristics	3 - 4
III. Pathway and Environmental Hazard Assessment	4 - 7
IV. Summary and Conclusion	7 - 8
V. Figures	9
Figure 1: Vicinity Map	10
Figure 2: Site Map	11
Figure 3: Study Radius and Groundwater Wells map	12
VI. Photodocumentation	13 - 19
VII. List of References	20 - 21
VIII. References	22

## I. Introduction

The Oklahoma State Department of Health (OSDH) is tasked by the U.S. Environmental Protection Agency (EPA), as authorized by CERCLA and as amended by SARA, under the Multi-Site Cooperative Agreement (CA# V-00645-01) to conduct a preliminary assessment (PA) of the Acme Brick Strip Mines site, (CERCLIS ID # not yet assigned). The primary purpose of this PA is to assess the immediate or potential threat of wastes at the site that may have an impact on public and environmental health; and to collect information sufficient to support a decision regarding the need for further action under CERCLA/SARA. The scope of this investigation includes the review of available information from an interview with the current property owner, and conducting a comprehensive target survey.

## II. Site Description, Operational History, and Waste Characteristics

### *Site Description*

The Acme Brick Strip Mine site is located in the NE4 SE4 NE4 SEC 31 and SW4 NW4 SEC 32 T22N R14E Tulsa County, Oklahoma (Reference 1). The site has the coordinates of 36° 20' 45.59" north latitude and 95° 50' 51.28" west longitude (Reference 2). The site is located about a 1/2 mile south of the City of Collinsville. This site is estimated to be 50 acres in size and is located in both a rural and suburban area (Reference 3). Flanking the east side of the site are railroad tracks and "Old" U.S. Highway 169. On the other sides, the site is surrounded by agricultural lots (Reference 3). To the east of "old" highway 169 is a mobile home trailer park with six (6) trailers (Reference 3). A residence is located on-site on the former office building of the smelter operation on-site (Reference 3). The property owner, which lives on-site, is Francis Sharp (Reference 4). Her mailing address is Box 23, Collinsville Oklahoma (Reference 4). The on-site residence has an active water well, allegedly fifty (50) feet deep and having a water level of 35 feet (Reference 3). According to the resident, this well was drilled in 1942 (Reference 5).

### *Operational History*

Located at the Acme Brick Strip Mines site is the former Tulsa Fuel & Manufacturing Company, smelters of zinc and roasters of lead (Reference 3). For this reason, the site will for the remainder of this report, be referred to as **Tulsa Fuel and Manufacturing Company (TFM)**. According to the current property owner, the Tulsa Fuel & Manufacturing Co. began operating in 1914 and ceased operations in 1925 (Reference 3, 5). Prior use of the land before the smelting operation is unknown (Reference 5). The resident moved on-site on July 1, 1935 and has lived at this location up to the present (Reference 3). The former smelting operation utilized nine (9) furnaces, approximately one-hundred (100) feet in length, and believed to be fueled by natural gas from nearby wells (Reference 6). In addition, large amounts of ore were stored on-site in the northeastern area of the site, as well as a laboratory of some type was utilized on-site (Reference 6). Also, a 2 million gallon capacity reservoir was used in

conjunction with a condenser room during smelting operations (Reference 6). In the surrounding area of the site, surface mining activity was considerable. Immediately south of the site was a surface mining operation about forty (40) acres in size (Reference 3, 7).

#### *Waste Characteristics*

The wastes of concern are those associated with the practice of smelting zinc and roasting of lead. Due to there being a laboratory on-site during the plant's operation, and no information as to how material in the laboratory were handled, possible waste associated with the laboratory are also of concern. As seen during the site reconnaissance, the majority of the site, about forty (40) acres, is covered with black smelter residue (Reference 3). The depth of this material is unknown. In addition, two (2) ponds in the northern area of the site and a surface water impoundment immediately south of the site are likely to contain surface water runoff from the site. Consequently, the smelter residue is mostly likely associated with sediments in these impoundments. Therefore, the impoundments are likely to be sources of waste too. The two (2) impoundments in the northern area of the site are about five (5) and seven (7) acres in size each; and the water-filled pit to the south of the site is about thirty (30) acres in size (Reference 7).

### **III. Pathway and Environmental Hazard Assessment**

#### *Groundwater*

The site sits atop the Okemah-Parsons-Carytown soil complex (Reference 8). This complex is characterized as being found at depths up 68 inches below land surface, and a permeability ranging between 0.06 - 2.0 inches per hour (Reference 8). These soils are formed in loamy and clayey materials (Reference 8). Underlying this soil complex is the Seminole Formation. This formation is characterized as consisting of shale, sandstone, and thin coal beds (Reference 8). Underlying the Seminole Formation is the Nowata Formation. This formation consists of shale, minor sandstone, and limestone (Reference 8). Next is the Oologah Formation. It too consist of limestone and shale (Reference 8). Wells in the area of the site commonly yield only small amounts of fair-to-poor quality of water (Reference 8).

There are no public water supply wells within the four (4) mile study radius of the site (Reference 9). In addition, thirteen (13) private wells are located within the four (4) mile study radius, including the on-site and active private well (Reference 3, 10, 11). Populations served by these private wells are described below (Reference 10, 11, 12). The depth to groundwater ranges from five (5) to thirty (30) feet below ground surface (Reference 8). The City of Collinsville, located approximately 1/2 mile north of the site, utilizes Lake Oologah as its public water supply (Reference 13). The general vicinity outside the city's water service area is served by the Washington County Rural Water District No. 3 (Reference 14). Due to the unknown depth of waste on-site, particularly the large amount of smelter residue waste; groundwater users on-site are considered primary targets. The remaining wells within the study radius are considered secondary targets.



Distance from site (mi)	Estimated Population Served By Private Wells
On-site	* 2.0
0 - 1/4	0
1/4 - 1/2	0
1/2 - 1	0
1 - 2	** 4.86
2 - 3	** 9.72
3 - 4	** 14.58
<b>TOTAL</b>	<b>31.16</b> (no. Of primary targets = 2) (no. of secondary targets = 29.16)

Sources: References 10, 11, 12

\* primary targets

\*\* secondary targets

### Surface Water

The nearest perennial stream is about 0.75 miles northeast and downstream from the site, and is referred to as Blackjack Creek (Reference 15). Originating in the northeastern area of the site is an intermittent stream which drains into Blackjack Creek (Reference 3, 15 site recon and topo map). Immediately south of the site is a large water-filled pit most likely associated with the now inactive adjacent surface mining operations (Reference 3, 15). It is likely that this water-filled pit is in communication with the on-site intermittent stream, and is likely to receive surface water runoff from the site (Reference 15). Consequently, release to surface water is suspected. However, there are no surface water intakes within the fifteen (15) mile target distance (Reference 16). The probable point of entry (PPE) into Blackjack Creek is located in the NE4 NE4 NE4 SEC 32 T22N R14E (Reference 15). The 15-mile target distance ends in the Caney River, specifically the NE4 NE4 NW4 SEC 20 T22N R15E (Reference 7). The normal annual total precipitation in the site's region is about forty (40) inches per year (Reference 17). The site does not lie within the 500 year flood plain (Reference 18).

There may be as much as thirty (30) miles of wetland frontage area associated with the surface water pathway (Reference 7). Surface waters considered to be fisheries are The Caney River and Blackjack Creek. The fisheries are considered primary targets.

Habitats of the endangered/threatened species listed below are known to be in Tulsa and/or Rogers county(s) (Reference 19). Due to the fact that the site is located in a somewhat rural area, the potential exists for these species to be on-site, and are considered primary targets (Reference 3). In addition, there has been an occurrence of the Prairie Mole Cricket within four (4) miles of the site (Reference 20).

<i>Species</i>	<i>Federal Status</i>
Peregrine falcon	Endangered
Bald eagle	Endangered
Interior least tern	Endangered
Piping plover	Threatened
Prairie mole cricket	Proposed Threatened
Paddlefish	Candidate
Arkansas River shiner	Candidate
Arkansas River speckled chub	Candidate
Texas horned lizard	Candidate
White-faced ibis	Candidate
Long-billed curlew	Candidate
Western Snowy plover	Candidate
Migrant loggerhead shrike	Candidate
Ozark chinquapin	Candidate
Western prairie fringed orchid	Threatened
Arkansas darter	Candidate
Alligator snapping turtle	Candidate
Ferruginous hawk	Candidate

#### *Soil Exposure*

Substances of concern in this pathway are the unconfined soils and smelter residues most likely contaminated with heavy metals (Reference 3). Additionally, other substances associated with the on-site laboratory, and condenser room may also be of concern. As in all preliminary assessments, soil contamination is always assumed. There is an on-site residence with the population of two (2) (Reference 3). Since the site is located in a somewhat rural area, it is assumed in this investigation that the terrestrial species listed under the surface water pathway may exist on-site (Reference 3).

#### *Air*

The site is sparsely vegetated and vegetation present appears stressed. As mentioned earlier, the site is mostly covered with what appears to be a type of black smelter residue (Reference 3). Consequently, particulates associated with these residues would be likely to become sus-

pendent in the atmosphere. In addition, due to the fact that the smelter operated in the early 1900s, thus lacking air emission standards, suspended particulates and "fallout" may be found in an extended area from the site. The estimated population and wetland acreage within four (4) miles from the site is described below (References 7, 21), and are considered primary targets due to the information stated previously. It is assumed that the habitats of endangered/threatened species listed under the surface water pathway may be within the four mile study radius, and potentially on-site since the site consist of several large trees, impoundments, and some grasses (Reference 3).

Distance from site (mi)	Est. Population	Est. Wetland Acreage
On-site	2	3
0 - 1/4	29.16	12
1/4 - 1/2	99.63	13
1/2 - 1	1322	30
1 - 2	3241	110
2 - 3	4883	249
3 - 4	311	403
<b>TOTAL</b>	<b>9887.79</b>	<b>820</b>

#### IV. Summary and Conclusion

The Tulsa Fuel & Manufacturing Company allegedly began operating in 1914 and ceased operation in 1925. Due to the unknown depth of waste on-site, ground water in the vicinity may have been affected. Surface water has a potential for contamination due to the high potential for runoff to be discharged into on-site and off-site streams, thus posing a threat to the environment and to human targets through food chain contamination. Even though controlled access does exist, contamination appears to be wide spread on-site and human exposure to contaminated soils exists. In addition, since the site is not adequately covered by well established vegetation or by other means and has operated as a smelter, an air release is suspected.

At the time of the site discovery project, this site was referred to as Acme Brick Strip Mines. During the course of the Preliminary Assessment, it was found that Tulsa Fuel & Manufacturing operated the smelting operation on-site. For this reason, it is recommended that this site be referred to as the **Tulsa Fuel & Manufacturing Company**.

## RECORD OF COMMUNICATION

Date: October 30, 1992  
To: Acme Brick Strip Mine PA file  
From: David S. Crow, OSDH Environmental Specialist *DC*  
Subject: Acme Brick Strip Mine site reconnaissance

On October 29, 1992, Richard Brooks and myself travelled to Collinsville for the purpose of conducting an on/off-site reconnaissance of the above site. We first stopped at the Tulsa City/County Health Department to meet Mark Flemming. He accompanied us to the site. At the time of our reconnaissance, the weather was cool and drizzly.

Upon reaching the site, we met Ms. Francis Peters, the current owner of the site, and who we assume to be her husband. She once again asked why we were investigating her property. I explained to her that this site had been brought to our attention by a report done by the Department of Conservation in 1983. Based on information in the 1983 report, we determined that the smelter operation needed to be addressed because of a possible risk to public health and to the environment.

Ms. Peters and her husband informed us that their house is located on the foundation of the former office of the site. Also, they told us that they have a well located in their house that is about fifty (50) deep. Depth to groundwater is estimated to be about thirty-five (35) feet. Also, they told us that there is a water well west of their house that is about 200 feet deep. Ms. Peters showed us an insurance map of the site. This map showed in some detail, the entire site. According to this map, the name of the smelting operation is **Tulsa Fuel & Manufacturing Company, smelters of zinc and roasters of lead**. The map shows (in general terms) nine (9) furnaces about 100 feet in length, a 2 million gallon capacity reservoir, ore bins, a laboratory, mechanical building, condenser room, and an office. Also, from this map it appears that the furnaces were fueled by natural gas. In addition, since coal mining was in the area, we believe that these furnaces may also have been fueled by coal.

Ms. Peters further informed us that the smelter ceased operation in 1925, and that she moved to her present location, on-site, on July 1, 1935. Her husband told us that at one time he put some ducks in a pond east of their house, and the ducks died within a few days. He also said that horses, particularly colts, would not live on-site. The Peter's thoughts were that smelter waste was in the ponds and that the animals died as a result of this. I asked the Peter's how much land they owned on-site. They replied that they owned about 100 acres and that the smelter used about 80 acres of this 100 acres.

Next, we began walking most of the site. In the area of the Peter's home there appeared to be no stressed vegetation. However, the rest of the site is mostly void of vegetation, with the exception of some large trees, cattails, some grasses, and some type of moss growing in a few areas. Most of the site is covered with a black, volcanic ash looking material. There are two ponds in the northern area of the site. One of these believed to be the one where the ducks died. South of these ponds is what appears to be remnants of an old and large foundation. Also in this area is part of a demolished large concrete vent stack. At what appears to be the southern edge of site, is a large rectangular water impoundment. This

appears to be part of the former coal strip mining area that was located immediately south of the site. At the time of our reconnaissance, we saw two fish in these waters. Throughout the site there are mounds of soil, and also of the black volcanic ash looking material.

After lunch, Richard and I visited the Collinsville library to possibly locate any historical information about the site. We browsed through historical newspaper clippings, but found nothing significant. The librarian said that we should contact John Wright, the former owner of the city's newspaper, for possible information concerning the site. Next, we surveyed the 1/4 mile radius of the site for the number of residences. As a result of our efforts, we determined that there are about twelve (12) residences within 1/4 mile of the site. While surveying the nearby area, it seems that surface water sheet flow would flow in a east southeasterly direction. We concluded our reconnaissance at about 3:00 p.m..

## **V. Figures**

856 IN NW  
VERA

UNITED STATES  
DEPARTMENT OF THE INTERIOR  
GEOLOGICAL SURVEY





Figure 1  
Vicinity Map






## SITE MAP








Figure 2

# ACME\_BRICK SITE

## STUDY RADIUS



TUL\_ROG

-  County\_lines
-  Highways
-  Hydrography
-  Railroads
-  Roads
-  Domestic Well
-  SITE


NORTH



**Figure 3**

Source: Atlas GIS (Version 1.2)

Miles



## **VI. Photodocumentation**

*DSC*  
**Photographer:** David S. Crow  
**Date:** October 29, 1992

*RLB*  
**Witness:** Richard L. Brooks  
**Direction:** North



**Comments:** Photograph #1 (matches slide 33, roll #2) On-site residence. Residence is located on former foundation of the office associated with the past smelter operations. A Private drinking water well is located at this residence.

*D.S.C.*  
**Photographer:** David S. Crow

**Date:** October 29, 1992

*R.B.*  
**Witness:** Richard L. Brooks

**Direction:** East



**Comments:** Photograph #2 (matches slide #5, roll 1) Photo shows foundations associated with the smelter operation. This general area is covered with black smelter residue (particulates), with little or no vegetation.



**Photographer:** David S. Crow <sup>DSC</sup>  
**Date:** October 29, 1992

**Witness:** Richard L. Brooks <sup>RLB</sup>  
**Direction:** Southwest



**Comments:** Photograph #3 (matches slide #11, roll 1) Photo shows southern area of smelter operation. The general area is covered with black smelter residue, and remnants of fire brick. Also, occasional patches of vegetation are seen.

*D.S.C.*  
**Photographer:** David S. Crow  
**Date:** October 29, 1992

*R.B.*  
**Witness:** Richard L. Brooks  
**Direction:** Southwest



**Comments:** Photograph #4 (slide #13, roll 1) Photo shows water-filled pit believed to be a pit associated with the strip mining operation south of the site. The depth of this pit is unknown, but is considered to be used for recreational fishing.



*D.S.C.*  
**Photographer:** David S. Crow  
**Date:** October 29, 1992

*R.B.*  
**Witness:** Richard L. Brooks  
**Direction:** Southwest



**Comments:** Photograph #5 (matches slide #17, roll 1) Photo shows a close up view of the material found throughout most of the site. Objects seen in the picture are clay pots, furnace brick, and black smelter residue. This photo is representative of the majority of the site.



*D.S.C.*  
**Photographer:** David S. Crow  
**Date:** October 29, 1992

*RLB*  
**Witness:** Richard L. Brooks  
**Direction:** North



**Comments:** Photograph #6 (matches slide #3, roll 1) This photo shows what is believed to be the 2 million gallon reservoir associated with the smelter operation. This reservoir is located in the northern part of the site. The impoundment appears to be partially back-filled with smelter residue and other wastes associated with the site.

5011 8  
Site: Acme Brick, Collinsville  
Photographer: David Crow  
Witness: Richard Brooks  
Date: 10/29/92



5011 1  
Site: Acme Brick, Collinsville  
Photographer: David Crow  
Witness: Richard Brooks  
Date: 10/29/92



5011 1  
Site: Acme Brick, Collinsville  
Photographer: David Crow  
Witness: Richard Brooks  
Date: 10/29/92




5011 1  
Site: Acme Brick, Collinsville  
Photographer: David Crow  
Witness: Richard Brooks  
Date: 10/29/92



5011 1  
Site: Acme Brick, Collinsville  
Photographer: David Crow  
Witness: Richard Brooks  
Date: 10/29/92



Tulsa Fuel & Mart  
Collinsville OK



## VII. List of References

1. U.S. Environmental Protection Agency, *Potential Hazardous Waste Site Identification* form 2070-8 (5-8) for the Acme Brick Strip Mines site.
2. U.S. Environmental Protection Agency. *Standard Operating Procedure to Determine Site Latitude and Longitude Coordinates*. 1991. Calculation Worksheet for the Acme Brick Strip Mine site, Tulsa County, OK.
3. David S. Crow, OSDH. *Memorandum: On/Off-site Reconnaissance of the Acme Brick Strip Mine, Tulsa County, OK*. October 30, 1992.
4. David S. Crow, OSDH. *Record of Communication: Mike Sharp, Department of Mines, Oklahoma Conservation Commission*. October 23, 1992.
5. David S. Crow, OSDH. *Record of Communication: Francis Peters, current property owner of site*. November 9, 1992.
6. Sanborn Fire Insurance Map for *Tulsa Fuel & Manufacturing Company*, Collinsville, Oklahoma. February 1919.
7. Karen Khalafian, OSDH. *Wetland Acreage Worksheet, and accompanied references*. November 5, 1992.
8. David S. Crow, OSDH. *Memorandum: Groundwater and Hydrogeological information concerning the Acme Brick Strip Mine site, Tulsa County, OK*. November 4, 1992.
9. David S. Crow, OSDH. *Record of Communication: Public Water Supply inquiry to Terry Clingman, OSDH Water Quality Service*. October 7, 1992.
10. Request letter to Gary Glover, Oklahoma Water Resources Board. *Request for private and municipal well within study radius of site*. October 5, 1992.
11. Response fax from Scott Christensen, USGS Water Resources Division, *groundwater users within study radius of site*. November 10, 1992.
12. U.S. Department of Commerce. *Census Data for populations in Tulsa and Rogers Counties*. 1990.
13. David S. Crow, OSDH. *Memorandum: Public water supply information for the City of Collinsville*. November 4, 1992.
14. Washington County Rural Water District No. 3, *service map*.
15. U.S. Geological Survey. 15' Quadrangle map of Collinsville, OK. 1956.
16. David S. Crow, OSDH. *Record of Communication: Surface water intakes within 15-miles of probable point of entry (PPE)*. Gene Dousett, Oklahoma Water Resources Board. October 12, 1992.
17. United States Environmental Protection Agency. *Uncontrolled Hazardous Waste Site Ranking System Users Manual*. 1984.

18. David S. Crow, OSDH. *Request letter: Flood potential for Acme Brick Strip Mine site. Ken Morris, Oklahoma Water Resources Board.* October 1, 1992.
19. U.S. Fish and Wildlife Service. *Oklahoma Federal Listed of Proposed and Candidate Threatened and Endangered Species for Tulsa and Rogers counties.* June 1990.
20. Ian Butler, Oklahoma Biological Survey. Response letter from request made by Richard L. Brooks, OSDH, concerning possible endangered species at the Acme Brick Strip Mine site
21. Richard L. Brooks, OSDH. Geographical Exposure Modeling System (GEMS) for population distribution within the Acme Brick Strip Mine site's study radius. October 6, 1992.

## **VIII. References**

*Reference 1*



POTENTIAL HAZARDOUS WASTE SITE  
SITE IDENTIFICATION

I. IDENTIFICATION  
01 STATE 02 SITE NUMBER  
OKD

II. SITE NAME AND LOCATION

01 SITE NAME (Legal, common, or descriptive name of site) <i>Acme Brick Strip Mines</i>		02 STREET, ROUTE NO., OR SPECIFIC LOCATION IDENTIFIER <i>1/2 mi S. of Collinsville</i>			
03 CITY <i>Collinsville</i>	04 STATE <i>OK</i>	05 ZIP CODE <i>74021</i>	06 COUNTY <i>Tulsa</i>	07 COUNTY CODE	08 CONG. DIST.
09 DIRECTIONS TO SITE (Starting from nearest public road) <i>1/2 mile S. of Collinsville</i>					

III. RESPONSIBLE PARTIES

01 OWNER (if known) <i>Francis Sharp (on site)</i>		02 STREET (if known, residential, mailing) <i>Box 23 Collinsville OK</i>			
03 CITY <i>Collinsville</i>	04 STATE <i>OK</i>	05 ZIP CODE <i>74021</i>	06 TELEPHONE NUMBER <i>(b) (6)</i>		
07 OPERATOR (if known and different from owner) <i>none</i>		08 STREET (if known, residential, mailing)			
09 CITY	10 STATE	11 ZIP CODE	12 TELEPHONE NUMBER <i>( )</i>		
13 TYPE OF OWNERSHIP (Check one) <input checked="" type="checkbox"/> A. PRIVATE <input type="checkbox"/> B. FEDERAL: _____ (Agency name) <input type="checkbox"/> C. STATE <input type="checkbox"/> D. COUNTY <input type="checkbox"/> E. MUNICIPAL <input type="checkbox"/> F. OTHER: _____ (Specify) <input type="checkbox"/> G. UNKNOWN					

IV. HOW IDENTIFIED

01 DATE IDENTIFIED <i>1/1/83</i> MONTH DAY YEAR	02 IDENTIFIED BY (Check all that apply) <input type="checkbox"/> A. CITIZEN COMPLAINT <input type="checkbox"/> B. INDUSTRY <input type="checkbox"/> C. STATE/LOCAL GOVERNMENT <input type="checkbox"/> D. AERIAL RECONNAISSANCE <input type="checkbox"/> E. RCRA INSPECTION <input type="checkbox"/> F. SURFACE IMPOUNDMENT ASSESSMENT <input type="checkbox"/> G. OTHER EPA IDENTIFICATION <input checked="" type="checkbox"/> H. OTHER <i>Department of Conservation</i> (Specify)				
---	---	--	--	--	--

V. SITE CHARACTERIZATION

01 TYPE OF SITE (Check all that apply) <input type="checkbox"/> A. STORAGE <input type="checkbox"/> B. TREATMENT <input type="checkbox"/> C. DISPOSAL <input type="checkbox"/> D. UNAUTHORIZED DUMPING <input checked="" type="checkbox"/> E. OTHER <i>inoperative smelter</i> (Specify)		02 SUMMARY OF KNOWN PROBLEMS (Provide narrative description) <i>in operative smelting operation (zinc &amp; lead)</i>			
---	--	--	--	--	--

03 SUMMARY OF ALLEGED OR POTENTIAL PROBLEMS (Provide narrative description)

<i>wastes of smelting operation of concern</i>					
--	--	--	--	--	--

VI. INFORMATION AVAILABLE FROM

01 CONTACT		02 OF: <i>any Organization</i>		03 TELEPHONE NUMBER <i>( )</i>	
04 PREPARED BY <i>Bob Smith</i>	05 AGENCY <i>EPA Region 1</i>	06 ORGANIZATION	07 TELEPHONE NUMBER <i>(214) 655-6740</i>	08 DATE <i>12-8-92</i>	

*Reference 2*



**APPENDIX E**

**STANDARD OPERATING PROCEDURE  
TO DETERMINE SITE  
LATITUDE AND LONGITUDE COORDINATES**

**HAZARDOUS SITE EVALUATION DIVISION  
SITE ASSESSMENT BRANCH  
U.S. ENVIRONMENTAL PROTECTION AGENCY  
WASHINGTON, D.C.**

**September 1991**

LATITUDE AND LONGITUDE CALCULATION WORKSHEET #2  
LI USING ENGINEER'S SCALE (1/60)

SITE NAME: Acme Brick Strip Mines CERCLIS #: \_\_\_\_\_

AKA: \_\_\_\_\_ SSID: \_\_\_\_\_

ADDRESS: \_\_\_\_\_

CITY: \_\_\_\_\_ STATE: OK ZIP CODE: \_\_\_\_\_

SITE REFERENCE POINT: center of the site

USGS QUAD MAP NAME: Collinsville TOWNSHIP: 16 N/S RANGE: 14 E/W

SCALE: 1:24,000 MAP DATE: 1956 SECTION: NE 1/4 SE 1/4 NF 1/4

MAP DATUM: (1927) 1983 (CIRCLE ONE) MERIDIAN: SW 1/4 NE 1/4

COORDINATES FROM LOWER RIGHT (SOUTHEAST) CORNER OF 7.5' MAP (attach photocopy):

LONGITUDE: 95° 45' 00" LATITUDE: 36° 15' 00"

COORDINATES FROM LOWER RIGHT (SOUTHEAST) CORNER OF 2.5' GRID CELL:

LONGITUDE: 95° 50' 00" LATITUDE: 36° 20' 00"

CALCULATIONS: LATITUDE (7.5' QUADRANGLE MAP)

A) NUMBER OF RULER GRADUATIONS FROM LATITUDE GRID LINE TO SITE REF POINT: 138

B) MULTIPLY (A) BY 0.3304 TO CONVERT TO SECONDS:

$$A \times 0.3304 = \underline{45.59}''$$

C) EXPRESS IN MINUTES AND SECONDS (1' = 60''): 00° 45' 59"

D) ADD TO STARTING LATITUDE: 36° 20' 00.00" + 00° 45' 59" =

SITE LATITUDE: 36° 20' 45.59"

CALCULATIONS: LONGITUDE (7.5' QUADRANGLE MAP)

A) NUMBER OF RULER GRADUATIONS FROM RIGHT LONGITUDE LINE TO SITE REF POINT: 154

B) MULTIPLY (A) BY 0.3304 TO CONVERT TO SECONDS:

$$A \times 0.3304 = \underline{50.88}''$$

C) EXPRESS IN MINUTES AND SECONDS (1' = 60''): 00° 51' 28"


D) ADD TO STARTING LONGITUDE: 95° 50' 00.00" + 00° 51' 28" =

SITE LONGITUDE: 95° 50' 51.28"

INVESTIGATOR: Karen Khalafian DATE: 06/17/92

SITE NAME: Acme Brick Strip Mines

NUMBER: \_\_\_\_\_




TOPOGRAPHIC MAP QUADRANGLE NAME: Collinsville

SCALE: 1:24,000

COORDINATES OF LOWER RIGHT-HAND CORNER OF 2.5-MINUTE GRID:

LATITUDE: 36° 12' 00" LONGITUDE: 95° 50' 00"



# ROAD CLASSIFICATION

- Heavy-duty —————
- Medium-duty ————
- Light-duty ————
- Unimproved dirt =====
- U. S. Route (shield symbol)
- State Route (circle symbol)



COLLINSVILLE, OKLA.  
N3615-W9545/7.5

1956  
PHOTOREVISED 1973  
AMS 6856 IV SE-SERIES V883

F-62

(CATOOSA)  
6856 II NW

*Reference 3*



NOT TO SCALE

site boundaries

surface impoundments

intermittent stream

railroad tracks

Old State Hwy 169

foundation remnants


demolished vent stack

site is mostly covered with smelter slag waste

former strip pit (now water filled)

on-site residence  
former office

# SITE MAP



*Reference 4*

## RECORD OF COMMUNICATION

To: Acme Brick PA  
PA file

From: David S. Crow  
Environmental  
Specialist *DS*

Date: 10/23/92

Time: 3:40 p.m.

On October 23, 1992, I spoke to Mr. Mike Sharp of the Abandoned Mine Land Reclamation Program - Conservation Commission, via telephone concerning any information his office might have in regards to the property owner of the Acme Brick site. After checking his files, he found that Francis Sapp (aka Francis Peters) is the current property owner. The owner's mailing address is Box 23, Collinsville, OK 74021-003. The telephone number is (b) (6) He verified this information with the Tulsa Tax Assessor's office.

Mr. Sharp's office number is (405) 521-2384.



*Reference 5*

## OSDH RECORD OF COMMUNICATION

To: Acme Brick  
Strip Mine PA


From: David S. Crow, SC  
Environmental  
Specialist

Date: 11/9/92

Time: 0930

On the above stated date, I spoke to Ms. Francis Peters, the current property owner of the Tulsa Fuel & Manufacturing site in Collinsville. I asked her if she knew when the smelting operation began. According to Ms. Peters, the smelter began operating sometime in 1914. I also asked her if she knew what the land was used for prior to the smelter. She knew nothing of any prior use of the land. I also told her that in the near future, we would like to take a water sample of her well at her house. However, we are unsure when specifically we can sample the well due to the backlog of samples at the State laboratory. Ms. Peters told me that the well at their house was drilled in 1942.

*Reference 6*



## ENGINEER/REVIEWER

Concurrence: P. Waverly Morris 33193

SITE NAME : ACME BRICK STRIP MINES  
SITE LOCATION: COLLINSVILLE, OK  
SITE NUMBER : OKD987096195  
FILE LOG # : 186

ROUTE SLIP

HAZARDOUS WASTE SITE - INSPECTION REPORT

	INITIALS	DATE	TIME (HOURS)
1. MARK MCCASLAND	MEM	3/31/93	0
2. <del>WARREN NORRIS</del>	PN	3/31/93	-
3. JO TAYLOR (Cover memo, Xerox copies of report, log out of file, file) (Copies to Hickam, Wright 6H-ES)			

FILE CODE: SFD-24-1-4

BOOK REGISTER LOG #: 1876



## POTENTIAL HAZARDOUS WASTE SITE IDENTIFICATION

REGION  
VI

SITE NUMBER

OKD987096195

NOTE: The initial identification of a potential site or incident should not be interpreted as a finding of illegal activity or confirmation that an actual health or environmental threat exists. All identified sites will be assessed under the EPA's Hazardous Waste Site Enforcement and Response System to determine if a hazardous waste problem actually exists.

A. SITE NAME Acme Brick Strip Mines		B. STREET (or other identifier) U.S. Hwy 169	
C. CITY Collinsville	D. STATE OK	E. ZIP CODE 74021	F. COUNTY NAME Tulsa 143
G. OWNER/OPERATOR (if known) 1. NAME Unknown		2. TELEPHONE NUMBER	
H. TYPE OF OWNERSHIP (if known) <input type="checkbox"/> 1. FEDERAL <input type="checkbox"/> 2. STATE <input type="checkbox"/> 3. COUNTY <input type="checkbox"/> 4. MUNICIPAL <input type="checkbox"/> 5. PRIVATE <input checked="" type="checkbox"/> 6. UNKNOWN			
I. SITE DESCRIPTION  Most of the site is covered with what appears to be "spoil" from past surface mining operations. Also on-site there are two surface impoundments filled with water. The site is bordered to the east by railroad tracks and "old" US highway 169. The legal description is NE4 SE4 NE4 SEC 31 and SW4 NW4 SEC 32 T22N R14E.			
J. HOW IDENTIFIED (i.e., citizen's complaints, OSHA citations, etc.) OSDH site discovery project.			K. DATE IDENTIFIED (mo., day, & yr.) 7/28/92
L. SUMMARY OF POTENTIAL OR KNOWN PROBLEM  Wastes of concern appear to be waste associated with past surface mining operations. These wastes may be associated with the surface impoundment and spoil throughout the site.			
M. PREPARER INFORMATION			
1. NAME David S. Crow, OSDH, SC		2. TELEPHONE NUMBER (405) 271-7099	3. DATE (mo., day, & yr.) 9/2/92

## OSDH SITE DISCOVERY PROJECT CHECKLIST

Site Name: Aeme Brick Strip Mines

Site Location: Address \_\_\_\_\_  
City Collinsville  
County Tulsa  
Legal Sec 29, 31, 32 T20N R14E  
Latitude/ Longitude \_\_\_\_\_  
(S.O.P. attached)

Site Status: Active \_\_\_\_ (if active, enter number of workers seen \_\_\_\_)  
Inactive ☒

Site Description: Is waste evident (y/n) y, if so circle type(s) below -  
pile(s) surface water impoundment(s) contaminated soil(s)  
drum(s) tank(s) other \_\_\_\_\_

What other important structures not associated with the above waste(s) are seen onsite? \_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

Setting: (check all that apply) Rural ☒ or Urban \_\_\_\_

Industrial/ Commercial ☒

Agricultural ☒

Residential \_\_\_\_



**OSDH SITE DISCOVERY PROJECT CHECKLIST -cont-**

*Targets:* (circle all that are nearby the site, i.e. within a 1/4 mile)

Residence(s)      Daycare center(s)      Schools(s)      Workers(s)

Wetland(s)      Stream(s)      Lake(s)      Pond(s)      Municipal well(s)

Private well(s)      Endangered and/or threatened species      Park(s)

Other \_\_\_\_\_

*Additional Comments:*

Attachments:      Photodocumentation and S.O.P.  
Other \_\_\_\_\_

*Handwritten signature*

Site Discovery Photodocumentation

**Site Name:** Acme Brick Strip Mines

**Site Type:** Lead and Zinc Smelters

**Photographer:** Richard Brooks, OSDH

**Date Taken:** July 28, 1992



*Reference 7*

## WETLAND ACREAGE WORKSHEET

SITE: Acme Brick Strip Mine PA site, Collinsville, Oklahoma.

Listed below are the estimated wetland acreage within four miles of the stated site. The acreages was derived by summing all designated wetland areas for each study radius with the use of the "Wetland Acreage Guide" of the appropriate inventory maps.

STUDY RADIUS (mi)	ESTIMATED WETLAND SIZE (acres)
On-site	3
0 - 1/4	12
1/4 - 1/2	13
1/2 - 1	30
1 - 2	110
2 - 3	249
3 - 4	403
<b>TOTAL</b>	<b>820</b>

### Source of Information:

U.S. Department of Interior. *National Wetlands Inventory Quadrangle Maps:*


1. Vera, OK
2. Collinsville, OK
3. Oologah, OK
4. Tulsa SW, OK
5. Sperry, OK
6. Collinsville, OK

Compiled by:


Loree Khalafian

Date:


11/5/92




On-site  
about 3 acres




0 -  $\frac{1}{4}$  mi.  
about 12 acres




$\frac{1}{4}$  -  $\frac{1}{2}$  mi.  
about 13 acres




$\frac{1}{2}$  - 1 mi.  
about 30 acres





1 - 2 mi.  
about 110 acres



2 - 3 mi.  
about 249 acres




3 - 4 mi.  
about 403 acres




Acme Brick Strip Mines

$$\frac{1}{2} \text{ cm}^2 = 10 \text{ acres}$$







*Reference 8*



## MEMORANDUM

November 4, 1992

To: Acme Brick PA file

From: David S. Crow, OSDH Environmental Specialist *DSC*

This memorandum is to serve as reference for the attached material used in determining the Groundwater portion of the Acme Brick Preliminary Assessment. The sources used are the following:

1. USGS Hydrologic Atlas 2, *Reconnaissance of the Water Resources of the Tulsa Quadrangle Northeastern Oklahoma*. 1971
2. U.S. Department of Agriculture Soil Conservation Service, *Soil Survey of Tulsa County, Oklahoma*.

## OKLAHOMA GEOLOGICAL SURVEY

CHARLES J. MANKIN, *Director*


## HYDROLOGIC ATLAS 2

## RECONNAISSANCE OF THE WATER RESOURCES OF THE TULSA QUADRANGLE

## NORTHEASTERN OKLAHOMA

by

MELVIN V. MARCHER AND ROY H. BINGHAM

Prepared in cooperation with  
United States Geological SurveyScale  
1:250,000.University of Oklahoma  
Norman  
1971

quality water.

## COFFEYVILLE AND CHECKERBOARD FORMATIONS

*Coffeyville Formation*, shale and thin-bedded sandstone. Yields only small amounts of fair- to poor-quality water.

*Checkerboard Formation*, limestone and some shale. Yields only small amounts of fair- to poor-quality water.

## SEMINOLE FORMATION

Shale, sandstone, and thin coal beds. Yields only small amounts of fair- to poor-quality water.

## HOLDENVILLE AND LENAPAH FORMATIONS

(Map unit only in Tulsa County)

*Holdenville Formation*, shale and minor sandstone and limestone. Yields only small amounts of fair- to poor-quality water.

*Lenapah Formation*, limestone and shale. Yields only small amounts of fair- to poor-quality water.

## LENAPAH FORMATION

(Map unit only in Nowata County)

Limestone and shale. Yields only small amounts of fair- to poor-quality water.

## NOWATA FORMATION

Shale and minor sandstone and limestone. Yields only small amounts of fair- to poor-quality water.

## OOLOGAH FORMATION

Thin-bedded limestone and some shale in the southern part of the area. North of Oologah, in western Rogers County, the map unit, IPol, includes the following formations: *Altamont Formation*, limestone and minor shale; *Bandera Formation*, shale and thin sandstone; *Pawnee Formation*, limestone and minor shale. Yields only small amounts of fair- to poor-quality water.

## LABETTE FORMATION

Shale and thin sandstone and limestone. Yields only small amounts of fair- to poor-quality water.

## FORT SCOTT LIMESTONE

(Mapped with the Labette Formation south of Bird Creek in Tulsa County)

Limestone and shale. Yields only small amounts of fair- to poor-quality water.

## SENORA FORMATION

Shale with thin and lenticular sandstone, minor limestone, and coal. Yields only small amounts of fair- to poor-quality water, except for the Chelsea Sandstone Member near the base of the formation in Craig, Mayes, and Rogers Counties, which probably will yield small to moderate amounts of fair-quality water locally.

## BOGGY FORMATION

Shale, sandstone, and coal. Yields only small amounts of fair- to poor-quality water, except for the Bluejacket Sandstone Member at the base of the formation, which probably yields small to moderate amounts of fair-quality water locally.

## SAVANNA, McALESTER, HARTSHORNE, AND ATOKA FORMATIONS

IPsv *Savanna Formation*, shale and thin sandstone, limestone, and coal. Yields only small amounts of fair- to poor-quality water.

IPmh *McAlester and Hartshorne Formations*, shale and some sandstone and coal. Except for the Warner Sandstone Member at the base of the McAlester Formation, these units yield only small amounts of fair- to poor-quality water. The Warner Sandstone probably will yield small to moderate amounts of fair-

PENNSYLVANIAN



T 20N

15'

T 21N


T 22N

OSAGE CO

T 23N

10'

T 24N



*Larry J. McDonald*

# SOIL SURVEY OF Tulsa County, Oklahoma

---



**United States Department of Agriculture  
Soil Conservation Service**

**In cooperation with  
Oklahoma Agricultural Experiment Station**

SYMBOL	NAME
1	Apperson silty clay loam, 1 to 3 percent slopes
2	Apperson silty clay loam, 3 to 5 percent slopes
3	Bates loam, 1 to 3 percent slopes
4	Bates-Coweta complex, 3 to 5 percent slopes
5	Catoosa silt loam, 1 to 3 percent slopes
6	Catoosa-Rock outcrop complex, 1 to 8 percent slopes
7	Choska very fine sandy loam
8	Choska-Severn-Urban land complex
9	Cleora fine sandy loam
10	Coweta-Bates complex, 2 to 6 percent slopes
11	Coweta-Eram-Urban land complex, 3 to 12 percent slopes
12	Dennis silt loam, 1 to 3 percent slopes
13	Dennis silt loam, 3 to 5 percent slopes
14	Dennis silt loam, 2 to 5 percent slopes, eroded
15	Dennis-Carytown complex, 1 to 3 percent slopes
16	Dennis-Radley complex, 0 to 12 percent slopes
17	Dennis-Urban land complex, 0 to 5 percent slopes
18	Enders-Hector complex, 5 to 30 percent slopes
19	Eram silty clay loam, 3 to 5 percent slopes
20	Eram-Coweta complex, 5 to 15 percent slopes
21	Glenpool loamy fine sand, 3 to 15 percent slopes
22	Hector-Linker complex, 1 to 5 percent slopes
23	Kemie loamy fine sand, 3 to 8 percent slopes
24	Kemie fine sandy loam, 1 to 3 percent slopes
25	Kemie-Urban land complex, 1 to 8 percent slopes
26	Kanima soils, 3 to 50 percent slopes 1/
27	Kiamia soils 1/
28	Larton-Glenpool complex, 0 to 3 percent slopes
29	Latimer clay
30	Lula silt loam, 1 to 3 percent slopes
31	Mason silt loam
32	Newtonia silt loam, 1 to 3 percent slopes
33	Newtonia silt loam, 3 to 5 percent slopes
34	Niotaze-Darnell complex, 3 to 15 percent slopes
35	Niotaze-Darnell complex, 15 to 25 percent slopes
36	Niotaze-Darnell complex, 25 to 45 percent slopes
37	Niotaze-Darnell-Urban land complex, 3 to 25 percent slopes
38	Oil-waste land
39	Okay loam, 0 to 1 percent slopes
40	Okay loam, 1 to 3 percent slopes
41	Okay loam, 3 to 5 percent slopes
42	Okay loam, 2 to 5 percent slopes, eroded
43	Okemah silt loam, 0 to 1 percent slopes
* 44	Okemah-Antons-Carytown complex, 0 to 1 percent slopes
45	Osage silty clay
46	Pitts
47	Radley silt loam
48	Radley soils 1/
49	Severn very fine sandy loam
50	Shidler-Rock outcrop complex, 1 to 12 percent slopes
51	Tallahassee fine sandy loam
52	Urban land
53	Wynona silty clay loam
54	Wynona-Urban land complex

### **Parsons Series**

The Parsons series consists of deep, very slowly permeable, nearly level soils on uplands. These soils formed in loamy and clayey material under a cover of grasses. The water table is at a depth of 0.5 to 1.5 feet during December through April.

Representative profile of Parsons silt loam, in an area of Okemah-Parsons-Carytown complex, 0 to 1 percent slopes, 120 feet south and 150 feet west of the northeast corner of sec. 23, T. 18 N., R. 13 E.:

### **Okemah Series**


The Okemah series consists of deep, slowly permeable, nearly level soils on uplands. These soils formed in loamy and clayey sediments weathered from shales under a cover of native grasses. The water table is at a depth of 2 to 3 feet during December through April.

Representative profile of Okemah silt loam, 0 to 1 percent slopes, 800 feet west and 150 feet south of the northeast corner of sec. 12, T. 22 N., R. 13 E.:

### **Carytown Series**

The Carytown series consists of deep, very slowly permeable, nearly level through very gently sloping soils on uplands. These soils formed in loamy and clayey material under a cover of prairie grasses. The water table is at a depth of less than 1 1/2 feet for brief to long periods during December through April.

Representative profile of Carytown silt loam, in an area of Okemah-Parsons-Carytown complex, 0 to 1 percent slopes, 1,350 feet north and 60 feet west of the southeast corner of sec. 3, T. 19 N., R. 14 E.:







*Reference 9*

## RECORD OF COMMUNICATION

**TO:** Appropriate PA files

**FROM:** David S. Crow, OSDH *D.S.C.*

**DATE:** October 7, 1992

**Re:** PA sites for FFY93 that have no PWS locations within the 4-mile study radius.

*OSDH*  
According to Terry Clingman, Water Quality Service, the following sites **do not** have any PWS locations within the 4-mile study radius.

Petroleum Electronics Mfg. Inc., Tulsa County

Power Electronics Mfg. Inc., Tulsa County

Precision Chrome Co., Tulsa County

Acme Brick Strip Mines, Tulsa County

*Reference 10*

October 5, 1992

Gary Glover, Hydrologist  
Ground Water Division  
Oklahoma Water Resources Board  
6000 N. Harvey  
P.O. Box 150  
Oklahoma City, OK 73101-150

Dear Mr. Glover:

The purpose of this letter is to request all copies of domestic well logs for both **private** and **municipal** wells that are presumably active and are in the locations specified in the attached tables. Please include copies from your current files, archive files, and permit application files. (Copies of well logs are preferred since they contain local geological information).

Copies of the well logs may be sent to the Oklahoma State Department of Health (OSDH) through interagency mail. The information provided by your office will be used to describe groundwater targets for each preliminary site assessment conducted by the OSDH, as authorized by a cooperative agreement with the U. S. Environmental Protection Agency.

If you have any questions or comments, please call me at (405) 271-7099, or Richard Brooks at (405) 271-7049.

Sincerely,

A handwritten signature in black ink, appearing to read "David S. Crow". The signature is fluid and cursive, with the first name "David" being more prominent.

David S. Crow  
Environmental Specialist

Enclosures (18)

**WELL LOG REQUEST**

for the

**Acme Brick Strip Mines Site**

<b>Active (Private and Municipal) Domestic Wells</b>				
<b>County(s)</b>	<b>Township</b>	<b>Range</b>	<b>Meridian</b>	<b>Sections</b>
Tulsa	21N	13E	IM	1 - 3, 10 - 14, 24.
Tulsa Rogers	21N	14E	IM	1 - 11, 14 - 21.
Tulsa	22N	13E	IM	12 - 15, 22 - 27, 34 - 36.
Tulsa Rogers	22N	14E	IM	7 - 10, 14 - 36.

STATE OF OKLAHOMA  
**MULTI-PURPOSE WELL REPORT**  
OKLAHOMA WATER RESOURCES BOARD  
1000 N.E. 10th St., P.O. Box 53585  
Oklahoma City, Oklahoma 73152

# 24753

1. WELL OWNER Dennis Bowers, 11006 N. 92nd E. Ave, Owasso, Ok, 74055 PHONE 918-272-0969  
2. LEGAL DESCRIPTION SW 1/4 of NE 1/4 of SE 1/4 of sec. 12, TWP. 21N S. RGE 13E EIM (Circle One) WIM ECM COUNTY Tulsa  
FINDING LOCATION Lot 5, Block 2, Country Estates  
Blocks or distance(s) from given point(s).

3. TYPE OF WORK  
☒ New Well ☐ Plugging  
☐ Reconditioning Work  
☐ Monitoring  
☐ Test Hole  
☐ Other \_\_\_\_\_  
4. USE  
☒ Domestic  
☐ Stock  
☐ Monitoring  
☐ Test Hole  
☐ Other \_\_\_\_\_  
NON-DOMESTIC  
☐ Irrigation  
☐ Municipal  
☐ Industrial  
☐ Commercial  
☐ Other \_\_\_\_\_  
5. DRILLING METHOD  
☐ Fluid Rotary ☐ Rev. Rotary  
☐ Cable ☐ Other \_\_\_\_\_  
☒ Air Rotary  
☐ H.S. Auger

**LOCATION PERMIT**

If this well is Non-Domestic, has the location been permitted?  
☐ Yes ☐ No Permit No. \_\_\_\_\_

**NEW WELL CONSTRUCTION DATA**

DATES: Started 5-6-91 Completed 5-6-91  
Contractor Knott's Water Well Drilling  
Driller Dale Knott  
Diameter Hole 8 in Total Depth 200 ft.

**CASING RECORD**

Diameter From To  
Surface Pipe 5 in. 200 ft. +2 ft.  
Well Casing 5 in. 200 ft. +2 ft.  
Cement Grout Surface Seal? ☒ Yes ☐ No  
Type of Surface Seal: Portland Depth of Seal: 10 ft.

GRAVEL PACK:  
Gravel Packed From 200 ft. to 10 ft.  
Amount Used: 2T

**PERFORATION RECORD**

1/32" Type/Size  
slotted From 197 ft. To 160 ft.  
From \_\_\_\_\_ ft. To \_\_\_\_\_ ft.  
From \_\_\_\_\_ ft. To \_\_\_\_\_ ft.

**WELL TEST DATA**

Static Water Level 105 ft.  
Below Land Surface 105 ft.  
Approximate Yield 10 gpm.  
If Artesian: Flows 200 mg/l salt; 9g hard; gpm.  
10. PUMP INFORMATION  
Pump Type Submersible  
Power Source Electric  
Rated Capacity 10 gpm.  
Depth of Bowls or Cylinder 190 ft.

**PLUGGING DATA**


Date Plugged \_\_\_\_\_  
Backfilled With \_\_\_\_\_ Material To \_\_\_\_\_ ft.  
Grouted or Cemented From \_\_\_\_\_ Ft. To \_\_\_\_\_ ft.

**RECONDITIONING WORK**

Date Completed \_\_\_\_\_  
Replaced Casing From \_\_\_\_\_ ft. To \_\_\_\_\_ ft.  
Replaced Screen From \_\_\_\_\_ ft. To \_\_\_\_\_ ft.  
Deepened Well From \_\_\_\_\_ ft. To \_\_\_\_\_ ft.  
Redeveloped Well By \_\_\_\_\_

**CERTIFICATION**

The work described above was done under my supervision, and this report is true and correct to the best of my knowledge.  
Name Kathleen Knott License # WD 74  
Address Rt. 1, Telford, Ok, 74081 Phone # 865-3546  
Signed Kathleen Knott Date 5-7-91





STATE OF OKLAHOMA  
**MULTI-PURPOSE WELL REPORT**  
OKLAHOMA WATER RESOURCES BOARD  
1000 N.E. 10th St., P.O. Box 53585  
Oklahoma City, Oklahoma 73152

#26102

1. WELL OWNER Ruth Ann Ratcliff, 10602 N. 97th E. Ave., Owasso, OK, 74055 PHONE (918)272-5293

2. LEGAL DESCRIPTION SE 1/4 of SE 1/4 of 12 21N N 13E EIM (Circle One) WIM Tulsa  
ECM COUNTY

FINDING LOCATION

Blocks or distance(s) from given point(s).

3. TYPE OF WORK

☒ New Well ☐ Plugging  
☐ Reconditioning Work  
☐ Monitoring  
☐ Test Hole  
☐ Other

4. USE

☒ Domestic  
☐ Stock  
☐ Monitoring  
☐ Test Hole  
☐ Other

NON-DOMESTIC

☐ Irrigation  
☐ Municipal  
☐ Industrial  
☐ Commercial  
☐ Other

5. DRILLING METHOD

☐ Fluid Rotary ☐ Rev. Rotary  
☐ Cable ☐ Other  
☒ Air Rotary  
☐ H.S. Auger

6. LITHOLOGIC LOG

Material	From	To	Saturated
Top soil	0	1	
Clay	1	20	
Gray shale	20	62	
Gray sandy shale	62	72	
Gray shale	72	78	
Gray sandy shale	78	82	
Gray sand rock	82	140	7 gpm
Gray shale	140	145	

7. LOCATION PERMIT

If this well is Non-Domestic, has the location been permitted?

☐ Yes ☐ No Permit No. \_\_\_\_\_

8. NEW WELL CONSTRUCTION DATA

DATES: Started 8-14-91 Completed 8-14-91

Contractor Knott's Water Well Drilling

Driller Dale Knott

Diameter Hole 8 in. Total Depth 145 ft.

CASING RECORD

Diameter From To

Surface Pipe \_\_\_\_\_ in. \_\_\_\_\_ ft. \_\_\_\_\_ ft.

Well Casing 5 in. 145 ft. +2 ft.

Cement Grout Surface Seal? ☒ Yes ☐ No

Type of Surface Seal: Portland Depth of Seal: 10 ft.

GRAVEL PACK:

Gravel Packed From 145 ft. to 10 ft.

Amount Used: 1 1/2 T

PERFORATION RECORD

Type/Size  
1/32" slotted From 143 ft. To 105 ft.

From \_\_\_\_\_ ft. To \_\_\_\_\_ ft.

From \_\_\_\_\_ ft. To \_\_\_\_\_ ft.

9. WELL TEST DATA

Static Water Level \_\_\_\_\_ ft.

Below Land Surface 75 ft.

Approximate Yield 7 gpm.

If Artesian: Flows \_\_\_\_\_ gpm.

250 mg/l salt; 18g hard;

10. PUMP INFORMATION

Pump Type Submersible

Power Source Electric

Rated Capacity 10 gpm.

Depth of Bowls or Cylinder 135 ft.

11. PLUGGING DATA

Date Plugged \_\_\_\_\_

Backfilled With \_\_\_\_\_ Material To \_\_\_\_\_ ft.

Grouted or Cemented From \_\_\_\_\_ Ft. To \_\_\_\_\_ ft.

12. RECONDITIONING WORK

Date Completed \_\_\_\_\_

Replaced Casing From \_\_\_\_\_ ft. To \_\_\_\_\_ ft.

Replaced Screen From \_\_\_\_\_ ft. To \_\_\_\_\_ ft.

Deepened Well From \_\_\_\_\_ ft. To \_\_\_\_\_ ft.

Redeveloped Well By \_\_\_\_\_

13. CERTIFICATION

The work described above was done under my supervision, and this report is true and correct to the best of my knowledge.

Name Kathleen Knott License # WD 74

Address Rt. 1, Terilton, Ok 74081 Phone # 865-3546

Signed Kathleen Knott Date 7-15-91

Form 424-0887

USE ADDITIONAL SHEETS IF NECESSARY

White - Water Resources Board  
Canary - Drillers Copy  
Pink - Drillers Copy

STATE OF OKLAHOMA  
WATER RESOURCES BOARD  
1000 N.E. 10th St. P.O. Box 53585  
Oklahoma City, Oklahoma 73152

Application No. \_\_\_\_\_  
Aquifer \_\_\_\_\_  
Steam System Code \_\_\_\_\_  
Use Code \_\_\_\_\_  
County \_\_\_\_\_  
(Official Use Only)

MULTI-PURPOSE WATER WELL REPORT

#13201  
1. OWNER Harriet Hanklin ADDRESS P.O. Box 474  
Sperry OK 74073 PHONE 288-7686  
2. LEGAL DESCRIPTION OF WELL  
NW 1/4 of SW 1/4 of SE 1/4 of sec. 14; TWP. 21 S. Rge. 13 E1M WIM TULSA  
ECM; COUNTY TULSA

3. TYPE OF WORK  
☒ New Well ☐ Plugging  
☐ Reconditioning Work ☐ Test  
☒ PROPOSED ☐ PAST USE  
☒ Domestic ☐ Irrigation ☐ Stock  
☐ Municipal ☐ Industrial ☐ Test  
5. DRILLING METHOD  
☒ Rotary ☐ Rev. Rotary  
☐ Cable ☐ Other \_\_\_\_\_

6. LOG


Material	From	To	Saturated
SOIL	0	3	
CLAY	3	12	
SANDS	12	14	✓
CLAY	14	34	
SANDSTONE, BROKEN	34	40	✓
SANDSTONE	40	41	
SHALE	41	45	

RECEIVED  
SEP 5 1984  
Oklahoma Water Resources Board

RECEIVED  
AUG 28 1984  
Oklahoma Water Resources Board

7. NEW WELL CONSTRUCTION DATA  
Dates: Started 8/3/84 Completed 8/6/84  
Contractor CRABAR DRILLING  
Driller CRAIG TREIBER  
Diameter Hole 8 in. Total Depth 45 ft.  
CASING RECORD  
Diameter From To  
4 in. + 1 1/2 ft. 35 ft.  
Surface Seal: ☒ Yes ☐ No Type: Cement  
Depth of Seal: 11 ft.  
Gravel Packed: 8-12  
Gravel Packed From 45 ft. to 30 ft.  
Amount Used: 1/2 Ton  
PERFORATION RECORD  
Type Johnson 020 From 35 ft. To 40 ft.  
Size 4 1/2" x 9" From \_\_\_\_\_ ft. To \_\_\_\_\_ ft.  
" \_\_\_\_\_ From \_\_\_\_\_ ft. To \_\_\_\_\_ ft.

8. WELL TEST DATA  
Static Water Level Below Land Surface 24 ft.  
If Artesian: Flows \_\_\_\_\_ gpm.  
Water Temp. 61 °C/F Quality 94% WATER  
BAILER TEST  
Drawdown \_\_\_\_\_ ft. After Pumping \_\_\_\_\_ hrs. At \_\_\_\_\_ gpm.  
Size of Bailer: \_\_\_\_\_ gal.  
AIR LIFT PUMPING TEST 1 To 3 gpm  
Drawdown \_\_\_\_\_ ft. After Pumping 1 hrs. At \_\_\_\_\_ gpm.



9. PLUGGING DATA  
Date Plugged \_\_\_\_\_  
Backfilled With \_\_\_\_\_ Material To \_\_\_\_\_ ft.  
Grouted or Cemented From \_\_\_\_\_ ft. To \_\_\_\_\_ ft.  
Plot Location in Item 11. Show Distances From 2 Section Lines.

10. RECONDITIONING WORK  
Date Completed \_\_\_\_\_  
☐ Replaced Casing From \_\_\_\_\_ ft. To \_\_\_\_\_ ft.  
☐ Replaced Screen From \_\_\_\_\_ ft. To \_\_\_\_\_ ft.  
Deepened Well From \_\_\_\_\_ ft. To \_\_\_\_\_ ft.  
Redeveloped Well By \_\_\_\_\_

2. PUMP INFORMATION  
Pump Type To be installed by  
Power Source owner  
Rated Capacity \_\_\_\_\_ gpm.  
Depth of Bowls or Cylinder \_\_\_\_\_ ft.

13. CERTIFICATION  
The work described above was done under my supervision, and this report is true and correct to the best of my knowledge.  
Name CRAIG TREIBER License # WD-238  
Address 625 E 103 St. Tulsa Phone # 299-7709 or 9168  
Signed Craig Treiber Date 8/6/84

STATE OF OKLAHOMA  
WATER RESOURCES BOARD  
1000 N.E. 10th St., P.O. Box 53585  
Oklahoma City, Oklahoma 73152

Application No. \_\_\_\_\_  
Aquifer \_\_\_\_\_  
Steam System Code \_\_\_\_\_  
Use Code \_\_\_\_\_  
County \_\_\_\_\_  
(Official Use Only)

MULTI-PURPOSE WATER WELL REPORT

1. OWNER H. H. Daniel ADDRESS 11814 N. 136 E. Ave.  
Collinsville, Okla. PHONE 919-272-7387

2. LEGAL DESCRIPTION OF WELL  
NE 1/4 of SE 1/4 of SE 1/4 of sec. 5 TWP. 21 N Rge. 14 E COUNTY Tulsa

3. TYPE OF WORK  
☒ New Well ☐ Plugging  
☐ Reconditioning Work ☐ Test

4. PROPOSED / PAST USE  
☒ Domestic ☐ Irrigation ☐ Stock  
☐ Municipal ☐ Industrial ☐ Test

5. DRILLING METHOD  
☐ Rotary ☐ Rev. Rotary  
☒ Cable ☐ Other \_\_\_\_\_


6. LOG				7. NEW WELL CONSTRUCTION DATA	
Material	From	To	Saturated	Dates: Started <u>7/26/84</u> Completed <u>7/30/84</u>	
soil	0	2		Contractor <u>L. J. Jennings Drilling Co.</u>	
sandrock	2	120		Driller <u>Louis Jennings</u>	
				Diameter Hole <u>3</u> in. Total Depth <u>120</u> ft.	
( water 29, 61, & 115' )				CASING RECORD	
				5" PVC 200' in. 1' above ground. To 19 ft.	
				Surface Seal: <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No Type: <u>cement</u>	
				Depth of Seal: <u>19</u> ft.	
				Gravel Packed:	
				Gravel Packed From _____ ft. to _____ ft.	
				Amount Used: _____	
				PERFORATION RECORD	
				Type _____ From _____ ft. To _____ ft.	
				Size _____ From _____ ft. To _____ ft.	
				" _____ From _____ ft. To _____ ft.	

RECEIVED  
AUG 15 1984

8. WELL TEST DATA  
Static Water Level Below Land Surface 5 ft.  
If Artesian: Flows \_\_\_\_\_ gpm.  
Water Temp. 67 °F Quality good

9. PUMPING TEST  
Drawdown \_\_\_\_\_ ft. After Pumping \_\_\_\_\_ hrs. At \_\_\_\_\_ gpm.

10. RECONDITIONING WORK  
Date Completed \_\_\_\_\_  
☐ Replaced Casing From \_\_\_\_\_ ft. To \_\_\_\_\_ ft.  
☐ Replaced Screen From \_\_\_\_\_ ft. To \_\_\_\_\_ ft.  
Deepened Well From \_\_\_\_\_ ft. To \_\_\_\_\_ ft.  
Redeveloped Well By \_\_\_\_\_

11. PLAT  
10 AC. 

12. PUMP INFORMATION  
Pump Type \_\_\_\_\_  
Power Source \_\_\_\_\_  
Rated Capacity \_\_\_\_\_ gpm.  
Depth of Bowls or Cylinder \_\_\_\_\_ ft.

13. CERTIFICATION  
The work described above was done under my supervision, and this report is true and correct to the best of my knowledge.

Name Louis Jennings License # WD265  
Address RR 2 Box 96 Claremore, OK. Phone # 918-341-0195  
Signed [Signature] Date 8-8-84

STATE OF OKLAHOMA  
WATER RESOURCES BOARD  
1000 N.E. 10th St. P.O. Box 53585  
Oklahoma City, Oklahoma 73152

Application No. \_\_\_\_\_  
Aquifer \_\_\_\_\_  
Steam System Code \_\_\_\_\_  
Use Code \_\_\_\_\_  
County \_\_\_\_\_  
(Official Use Only)

MULTI-PURPOSE WATER WELL REPORT

#13205

1. OWNER John Klein ADDRESS 12584 E. 111 th St. North  
Owasso, Okla. 74055 PHONE \_\_\_\_\_

2. LEGAL DESCRIPTION OF WELL  
NW 1/4 of SE 1/4 of NE 1/4 of sec. 8 : TWP. 21 N Rge. 14 ~~XXX~~ COUNTY Tulsa

3. TYPE OF WORK  
☒ New Well ☐ Plugging  
☐ Reconditioning Work ☐ Test

4. PROPOSED / PAST USE  
☒ Domestic ☐ Irrigation ☐ Stock  
☐ Municipal ☐ Industrial ☐ Test

5. DRILLING METHOD  
☐ Rotary ☐ Rev. Rotary  
☒ Cable ☐ Other \_\_\_\_\_

LOG			
Material	From	To	Satur. rated ✓
soil	0	2	
sandy clay	2	12	
sand rock	12	113	x
water @ 90'			
shale	113	120	

7. NEW WELL CONSTRUCTION DATA  
Dates: Started 8-25-84 Completed 8-27-84  
Contractor L&S Jennings Drilling Co.  
Driller Louis Jennings  
Diameter Hole 12 in. Total Depth 120 ft.

CASING RECORD  
5" PVC 160 # \_\_\_\_\_ Diameter \_\_\_\_\_ From \_\_\_\_\_ To \_\_\_\_\_  
in. \_\_\_\_\_ ft. \_\_\_\_\_ ft.  
Surface Seal: ☒ Yes ☐ No Type: cement  
Depth of Seal: 11 ft.  
Gravel Packed: \_\_\_\_\_  
Gravel Packed From \_\_\_\_\_ ft. to \_\_\_\_\_ ft.  
Amount Used: \_\_\_\_\_

PERFORATION RECORD  
Type \_\_\_\_\_ From \_\_\_\_\_ ft. To \_\_\_\_\_ ft.  
Size \_\_\_\_\_ From \_\_\_\_\_ ft. To \_\_\_\_\_ ft.  
" \_\_\_\_\_ From \_\_\_\_\_ ft. To \_\_\_\_\_ ft.


8. WELL TEST DATA  
Static Water Level Below Land Surface 16 ft.  
If Artesian: Flows \_\_\_\_\_ gpm.  
Water Temp. 65 °F Quality good

BAILER TEST  
bailed dry let set 10 min. well made 40 gal.  
Drawdown \_\_\_\_\_ ft. After Pumping \_\_\_\_\_ hrs. At \_\_\_\_\_ gpm.  
Size of Bailer: 30 gal.

PUMPING TEST  
Drawdown \_\_\_\_\_ ft. After Pumping \_\_\_\_\_ hrs. At \_\_\_\_\_ gpm.

RECEIVED  
SEP 28 1984  
Oklahoma City

1. PLAT \_\_\_\_\_



NW 1/4 of SE 1/4 of NE 1/4 of SEC 8  
WP 21 N RGE 14 EIM XXXX

2. PUMP INFORMATION

Pump Type \_\_\_\_\_  
Power Source \_\_\_\_\_  
Rated Capacity \_\_\_\_\_ gpm.  
Depth of Bowls or Cylinder \_\_\_\_\_ ft.

9. PLUGGING DATA  
Date Plugged \_\_\_\_\_  
Backfilled With \_\_\_\_\_ Material To \_\_\_\_\_ ft.  
Grouted or Cemented From \_\_\_\_\_ ft. To \_\_\_\_\_ ft.  
Plot Location in Item 11. Show Distances From 2 Section Lines.

10. RECONDITIONING WORK  
Date Completed \_\_\_\_\_  
☐ Replaced Casing From \_\_\_\_\_ ft. To \_\_\_\_\_ ft.  
☐ Replaced Screen From \_\_\_\_\_ ft. To \_\_\_\_\_ ft.  
Deepened Well From \_\_\_\_\_ ft. To \_\_\_\_\_ ft.  
Redeveloped Well By \_\_\_\_\_

13. CERTIFICATION

The work described above was done under my supervision, and this report is true and correct to the best of my knowledge.

Name Louis Jennings License # WD265  
Address RR #2 box 96 Claremore, OK. Phone # 918-341-0195  
Signed [Signature] Date 9-27-84

# MULTI-PURPOSE WATER WELL REPORT

STATE OF OKLAHOMA  
WATER RESOURCES BOARD  
1000 N.E. 10th St., P.O. Box 53585  
Oklahoma City, Oklahoma 73152

Application No. \_\_\_\_\_  
Aquifer \_\_\_\_\_  
Steam System Code \_\_\_\_\_  
Use Code \_\_\_\_\_  
County \_\_\_\_\_ (Official Use Only)

#13202

1. OWNER BOB BRILEY ADDRESS 10324 N 127 E AVE  
OWASSO OK. PHONE \_\_\_\_\_

2. LEGAL DESCRIPTION OF WELL  
SW  $\frac{1}{4}$  of NE  $\frac{1}{4}$  of NE  $\frac{1}{4}$  of sec. 17; TWP. 21 N R. 14 E. ECM: COUNTY TULSA

3. TYPE OF WORK  
☒ New Well ☐ Plugging  
☐ Reconditioning Work  
☐ Test/Monitoring

4. USE  
☒ Domestic  
☐ Stock  
☐ Test Monitoring

NON-DOMESTIC  
☐ Irrigation  
☐ Municipal  
☐ Industrial  
☐ Commercial  
☐ Other

5. DRILLING METHOD  
☐ Rotary  
☐ Cable  
☒ Air  
☐ Rev. Rotary  
☐ Other

6. LOG			
Material	From	To	Saturated
CLAY	0	8	
SAND ROCK	8	32	
SOFT LIME	32	70	
LIME	70	71	
SOFT LIME	71	94	
SHALE	94	110	

7. LOCATION PERMIT  
If this well is Non-Domestic, has this location been permitted?  
☐ Yes ☐ No Permit No. \_\_\_\_\_

8. NEW WELL CONSTRUCTION DATA  
DATES: Started 11 JULY 86 Completed 12 JULY 86  
Contractor WAGNER WATER WELLS  
Driller C K WAGNER  
Diameter Hole 7 in. Total Depth 110 ft.

CASING RECORD  
Diameter From To  
Inside 4 1/2 in. 2 - 110 ft. 110 ft.  
Outside 6 in. 0 ft. 10 ft.  
Cement Grout Surface Seal ☒ Yes ☐ No  
Type of Surface Seal: \_\_\_\_\_ Depth of Seal: \_\_\_\_\_ ft.  
GRAVEL PACKED:  
Gravel Packed From 40 ft. to 110 ft.  
Amount Used: 55 GAL

PERFORATION RECORD  
Type Size  
125 SLOT From 50 ft. To 110 ft.  
From \_\_\_\_\_ ft. To \_\_\_\_\_ ft.  
From \_\_\_\_\_ ft. To \_\_\_\_\_ ft.

9. WELL TEST DATA  
Static Water Level Below Land Surface 35 ft.  
If Artesian: Flows \_\_\_\_\_ gpm.  
Approximate Yield 4 gpm.

10. PLUGGING DATA  
Date Plugged \_\_\_\_\_  
Backfilled With \_\_\_\_\_ Material To \_\_\_\_\_ ft.  
Grouted or Cemented From \_\_\_\_\_ ft. To \_\_\_\_\_ ft.  
Plot Location in Item 11. Show Distances From 2 Section Lines.

13. RECONDITIONING WORK  
Date Completed \_\_\_\_\_  
☐ Replace Casing From \_\_\_\_\_ ft. To \_\_\_\_\_ ft.  
☐ Replaced Screen From \_\_\_\_\_ ft. To \_\_\_\_\_ ft.  
Deepened Well From \_\_\_\_\_ ft. To \_\_\_\_\_ ft.  
Redeveloped Well By \_\_\_\_\_

14. CERTIFICATION  
The work described above was done under my supervision, and this report is true and correct to the best of my knowledge.  
Name C K WAGNER License # 209  
Address JAPULPA OK Phone 224-3257  
Signed C K Wagner Date 14 July 86

11. PLAT

10 AC.

SW  $\frac{1}{4}$  of NE  $\frac{1}{4}$  of NE  $\frac{1}{4}$  of SEC 17;  
VP 21 N R. 14 E. (Circle One)  
EIM, WIM, ECM

2. PUMP INFORMATION  
Pump Type SUB  
Power Source 220  
Rated Capacity 10 gpm.  
Depth of Bowls or Cylinder 103 ft.

# MULTI-PURPOSE WATER WELL REPORT

STATE OF OKLAHOMA  
WATER RESOURCES BOARD  
1000 N.E. 10th St., P.O. Box 53585  
Oklahoma City, Oklahoma 73152

Application No. \_\_\_\_\_  
Aquifer \_\_\_\_\_  
Stream System Code \_\_\_\_\_  
Use Code \_\_\_\_\_  
County \_\_\_\_\_ (Official Use Only)

#13208

1. OWNER Edward W. Coats ADDRESS Rt #1 Box 160-3  
Collinsville, Okla. 74021 PHONE 371-3169

## 2. LEGAL DESCRIPTION OF WELL

SE 1/4 of NW 1/4 of NE 1/4 of sec. 34; TWP. 22 S; RGE 13 E; COUNTY Tulsa

## 3. TYPE OF WORK

☒ New Well ☐ Plugging  
☐ Reconditioning Work  
☐ Test/Monitoring

## 4. USE

☒ Domestic  
☐ Stock  
☐ Test Monitoring

## NON-DOMESTIC

☐ Irrigation  
☐ Municipal  
☐ Industrial  
☐ Commercial  
☐ Other

## 5. DRILLING METHOD

☐ Rotary ☐ Rev. Rotary  
☒ Cable ☐ Other  
☐ Air

## 6. LOG

Material	From	To	Sam- pled
soil	0	1	
clay	1	12	
shale	12	32	
sandrock	32	85	

## 7. LOCATION PERMIT

If this well is Non-Domestic, has this location been permitted?

☐ Yes ☐ No Permit No. \_\_\_\_\_

## 8. NEW WELL CONSTRUCTION DATA

DATES: Started 7-6-86 Completed 7-12-86  
Contractor Lt S Jennings Drilling Co  
Driller Louis Jennings  
Diameter Hole 8 in. Total Depth 85 ft.

## CASING RECORD

Diameter From To  
Inside \_\_\_\_\_ in. \_\_\_\_\_ ft. \_\_\_\_\_ ft.  
Outside 5" 160# in. 1' above surface ft. 19 ft.  
Cement Grout Surface Seal ☐ Yes ☐ No  
Type of Surface Seal: Cement Depth of Seal: 19' ft.

## GRAVEL PACKED:

Gravel Packed From \_\_\_\_\_ ft. to \_\_\_\_\_ ft.  
Amount Used: \_\_\_\_\_

## PERFORATION RECORD

Type Size

\_\_\_\_\_ From \_\_\_\_\_ ft. To \_\_\_\_\_ ft.  
\_\_\_\_\_ From \_\_\_\_\_ ft. To \_\_\_\_\_ ft.  
\_\_\_\_\_ From \_\_\_\_\_ ft. To \_\_\_\_\_ ft.

## 9. WELL TEST DATA

Static Water Level Below Land Surface 26 ft.  
If Artesian: Flows \_\_\_\_\_ gpm.  
Approximate Yield 5 gpm.

## 10. PLUGGING DATA

Date Plugged \_\_\_\_\_  
Backfilled With \_\_\_\_\_ Material To \_\_\_\_\_ ft.  
Grouted or Cemented From \_\_\_\_\_ ft. To \_\_\_\_\_ ft.  
Plot Location in Item 11. Show Distances From 2 Section Lines.

## 13. RECONDITIONING WORK


Date Completed \_\_\_\_\_  
☐ Replaced Casing From \_\_\_\_\_ ft. To \_\_\_\_\_ ft.  
☐ Replaced Screen From \_\_\_\_\_ ft. To \_\_\_\_\_ ft.  
Deepened Well From \_\_\_\_\_ ft. To \_\_\_\_\_ ft.  
Redeveloped Well By \_\_\_\_\_

## 14. CERTIFICATION

The work described above was done under my supervision, and this report is true and correct to the best of my knowledge.

Name Louis Jennings License # W.D. 2265  
Address RR #2 Box 96 Claremore, OK Phone # 341-8195  
Signed [Signature] Date 10-1-86

## 11. PLAT



SE 1/4 of NW 1/4 of NE 1/4 of SEC 34; TWP. 22 S; RGE 13 E; COUNTY Tulsa

## 12. PUMP INFORMATION

Pump Type \_\_\_\_\_  
Power Source \_\_\_\_\_  
Rated Capacity \_\_\_\_\_ gpm.  
Depth of Bowls or Cylinder \_\_\_\_\_ ft.

White - Water Resources Board  
Canary - Drillers Copy  
Pink - Drillers Copy

STATE OF OKLAHOMA  
WATER RESOURCES BOARD  
1000 N.E. 10th St. P.O. Box 53585  
Oklahoma City, Oklahoma 73152

Application No. \_\_\_\_\_  
Aquifer \_\_\_\_\_  
Steam System Code \_\_\_\_\_  
Use Code \_\_\_\_\_  
County \_\_\_\_\_  
(Official Use Only)

#13209

MULTI-PURPOSE WATER WELL REPORT

1. OWNER Danny Geasland ADDRESS 9147 E. Okla Place  
Tulsa, OK 74115 PHONE \_\_\_\_\_  
2. LEGAL DESCRIPTION OF WELL EIM \_\_\_\_\_  
SW 1/4 of NW 1/4 of SE 1/4 of sec. 9 TWP. 22 N S. Rge. 14 E EGM: COUNTY Tulsa

3. TYPE OF WORK ☒ New Well ☐ Plugging  
☐ Reconditioning Work ☐ Test  
4. PROPOSED / PAST USE ☒ Domestic ☐ Irrigation ☐ Stock  
☐ Municipal ☐ Industrial ☐ Test ☒ Rotary ☐ Rev. Rotary  
☒ Cable ☐ Other \_\_\_\_\_

6. LOG


Material	From	To	Satu rated
Soil	0	1	
Sandy Clay	1	3	
Sand	3	19	
Shale	19	28	X
Slate	28	36	X
Shale	36	43	
Sandy Shale	43	76	
Sand	76	82	
Sandy shale	82	100	

RECEIVED  
JAN 10 1984  
Oklahoma Water Resources Board

RECEIVED  
JAN 5 1984  
Oklahoma Water Resources Board

7. NEW WELL CONSTRUCTION DATA  
Dates: Started 12/2/83 Completed 12/10/83  
Contractor L & S Jennings Drilling Co.  
Driller Louis Jennings  
Diameter Hole 10 in. Total Depth 100 ft.  
CASING RECORD  
Diameter From To  
5 in. 1' above ground 25 ft.  
Surface Seal: ☒ Yes ☐ No Type: Cement  
Depth of Seal: 25 ft. to surface  
Gravel Packed:  
Gravel Packed From \_\_\_\_\_ ft. to \_\_\_\_\_ ft.  
Amount Used: \_\_\_\_\_  
PERFORATION RECORD  
Type \_\_\_\_\_ From \_\_\_\_\_ ft. To \_\_\_\_\_ ft.  
Size \_\_\_\_\_ From \_\_\_\_\_ ft. To \_\_\_\_\_ ft.  
" \_\_\_\_\_ From \_\_\_\_\_ ft. To \_\_\_\_\_ ft.

8. WELL TEST DATA  
Static Water Level Below Land Surface 14 ft.  
If Artesian: Flows \_\_\_\_\_ gpm.  
Water Temp. 66 °C/F Quality good  
BAILER TEST  
Bailed hole dry. Makes 30 gal every 5 minutes  
Drawdown \_\_\_\_\_ ft. After Pumping \_\_\_\_\_ hrs. At \_\_\_\_\_ gpm.  
Size of Bailer: 35 gal. 9" bailer  
PUMPING TEST  
Drawdown \_\_\_\_\_ ft. After Pumping \_\_\_\_\_ hrs. At \_\_\_\_\_ gpm.



9. PLUGGING DATA  
Date Plugged \_\_\_\_\_  
Backfilled With \_\_\_\_\_ Material To \_\_\_\_\_ ft.  
Grouted or Cemented From \_\_\_\_\_ ft. To \_\_\_\_\_ ft.  
Plot Location in Item 11. Show Distances From 2 Section Lines.  
10. RECONDITIONING WORK  
Date Completed \_\_\_\_\_  
☐ Replaced Casing From \_\_\_\_\_ ft. To \_\_\_\_\_ ft.  
☐ Replaced Screen From \_\_\_\_\_ ft. To \_\_\_\_\_ ft.  
Deepened Well From \_\_\_\_\_ ft. To \_\_\_\_\_ ft.  
Redeveloped Well By \_\_\_\_\_

2. PUMP INFORMATION  
Pump Type Red Jacket  
Power Source 220 V  
Rated Capacity 10 gal min gpm.  
Depth of Bowls or Cylinder 93 ft.

13. CERTIFICATION  
The work described above was done under my supervision, and this report is true and correct to the best of my knowledge.  
Name Louis Jennings License # WD-265  
Address Rt. 2, Box 96 Phone # (918) 341-0195  
Claremore, OK 74017  
Signed \_\_\_\_\_ Date 12-28-83

White - Water Resources Board  
Canary - Drillers Copy  
Pink - Drillers Copy

STATE OF OKLAHOMA  
WATER RESOURCES BOARD  
1000 N.E. 10th St., P.O. Box 53585  
Oklahoma City, Oklahoma 73152

Application No. \_\_\_\_\_  
Aquifer \_\_\_\_\_  
Steam System Code \_\_\_\_\_  
Use Code \_\_\_\_\_  
County \_\_\_\_\_  
(Official Use Only)

MULTI-PURPOSE WATER WELL REPORT

NE

1. OWNER WALT MORRIS ADDRESS 15005 E. 131<sup>st</sup> ST. North  
Callinsville OK 74021 PHONE 371-5484  
2. LEGAL DESCRIPTION OF WELL  
SE  $\frac{1}{4}$  of NE  $\frac{1}{4}$  of NW  $\frac{1}{4}$  of sec. 34, TWP. 22 S; Rge. 14 E; COUNTY Regis

3. TYPE OF WORK ☒ New Well ☐ Plugging  
☐ Reconditioning Work ☐ Test  
4. PROPOSED / PAST USE ☒ Domestic ☐ Irrigation ☐ Stock  
☐ Municipal ☐ Industrial ☐ Test  
5. DRILLING METHOD ☒ Rotary ☐ Rev. Rotary  
☐ Cable ☐ Other \_\_\_\_\_

6. LOG			
Material	From	To	Satur. /
			rated
SOIL - CLAY	0	3	
SANDSTONE	3	14	
SHALE	14	17	
SANDSTONE	17	38	✓
SHALE	38	41	
SANDSTONE	41	46	✓
SHALE	46	49	
SANDSTONE	49	53	✓
SHALE	53	54 1/2	
SANDSTONE	54 1/2	60	✓
SHALE	60	61	
SANDSTONE	61	74	✓
COAL/BLACK SHALE	74	77	
SHALE	77	88	
SANDSTONE	88	99	?
SHALE	99	177	

7. NEW WELL CONSTRUCTION DATA  
Dates: Started 3-21-84 Completed 3-23-84  
Contractor CRAIG TRUBER  
Driller CRAIG TRUBER  
Diameter 8" - 97' to 177' Total Depth 177' ft.  
Casing Record  
Diameter From To  
4 in. 1 ft. 110 ft.  
Surface Seal: ☒ Yes ☐ No Type: Cement  
Depth of Seal: 12 ft.  
Gravel Packed: 38"  
Gravel Packed From 177 ft. to 12 ft.  
Amount Used: 1 3/4 Tons  
PERFORATION RECORD  
Type 1/4 SLOTS From 54 ft. To 74 ft.  
Size From 26 ft. To 100 ft.  
" From 36 ft. To 50 ft.

8. WELL TEST DATA  
Static Water Level Below Land Surface 27 1/2' ft.  
If Artesian: Flows \_\_\_\_\_ gpm.  
Water Temp. 60 °C/F Quality Good - some sulphur odor  
pH 7.6

BAILER TEST  
Drawdown \_\_\_\_\_ ft. After Pumping \_\_\_\_\_ hrs. At \_\_\_\_\_ gpm.  
Size of Bailer: \_\_\_\_\_ gal.


PUMPING TEST  
Drawdown \_\_\_\_\_ ft. After Pumping 1 1/2 hrs. At 78 gpm.

9. PLUGGING DATA  
Date Plugged \_\_\_\_\_  
Backfilled With \_\_\_\_\_ Material To \_\_\_\_\_ ft.  
Grouted or Cemented From \_\_\_\_\_ ft. To \_\_\_\_\_ ft.  
Plot Location in Item 11. Show Distances From 2 Section Lines.

10. RECONDITIONING WORK  
Date Completed \_\_\_\_\_  
☐ Replaced Casing From \_\_\_\_\_ ft. To \_\_\_\_\_ ft.  
☐ Replaced Screen From \_\_\_\_\_ ft. To \_\_\_\_\_ ft.  
Deepened Well From \_\_\_\_\_ ft. To \_\_\_\_\_ ft.  
Redeveloped Well By \_\_\_\_\_

13. CERTIFICATION  
The work described above was done under my supervision, and this report is true and correct to the best of my knowledge.  
Name CRAIG TRUBER License # WD-238  
Address 6605 E. 103 ST. South Tulsa Phone # 299-7909  
Signed Craig L. Truber Date 3-23-84

RECEIVED  
MAR 27 1984



SE  $\frac{1}{4}$  of NE  $\frac{1}{4}$  of NW  $\frac{1}{4}$  of SEC 34  
TWP 22 S; RGE 14 E; COUNTY Regis

12. PUMP INFORMATION  
Pump Type To Be Installed  
Power Source By  
Rated Capacity OWNER gpm.  
Depth of Bowls or Cylinder \_\_\_\_\_ ft.



White - Water Resources Board  
Canary - Drillers Copy  
Pink - Drillers Copy

STATE OF OKLAHOMA  
WATER RESOURCES BOARD  
1000 N.E. 10th St., P.O. Box 53585  
Oklahoma City, Oklahoma 73152

Application No. \_\_\_\_\_  
Aquifer \_\_\_\_\_  
Steam System Code \_\_\_\_\_  
Use Code \_\_\_\_\_  
County \_\_\_\_\_  
(Official Use Only)

MULTI-PURPOSE WATER WELL REPORT

1. OWNER Bob Bratton ADDRESS RR# 2 Box 882  
Collinsville, Okla. PHONE 918-371-3752

2. LEGAL DESCRIPTION OF WELL  
NW 1/4 of NW 1/4 of NW 1/4 of sec. 34 TWP. 22 N Rge. 14 ~~XXX~~ COUNTY Rogers

3. TYPE OF WORK  
☒ New Well ☐ Plugging  
☐ Reconditioning Work ☐ Test

4. PROPOSED / PAST USE  
☒ Domestic ☐ Irrigation ☐ Stock  
☐ Municipal ☐ Industrial ☐ Test

5. DRILLING METHOD  
☐ Rotary ☐ Rev. Rotary  
☒ Cable ☐ Other \_\_\_\_\_

6. LOG				7. NEW WELL CONSTRUCTION DATA	
Material	From	To	Saturated		
soil	0	2			Dates: Started <u>8-13-84</u> Completed <u>8-20-84</u>
sandrock	2	38	X		Contractor <u>I&amp;J Jennings Drilling Co.</u>
coal	38	39			Driller <u>Louis Jennings</u>
sandrock	39	80	X		Diameter Hole <u>12</u> in. Total Depth <u>103</u> ft.
sandy shale	80	103			

CASING RECORD

Diameter 5" PVC 200# From 1' above ground To 11 ft.  
Surface Seal: ☒ Yes ☐ No Type: cement  
Depth of Seal: 11 ft.  
Gravel Packed:  
Gravel Packed From \_\_\_\_\_ ft. to \_\_\_\_\_ ft.  
Amount Used: \_\_\_\_\_


PERFORATION RECORD

Type \_\_\_\_\_ From \_\_\_\_\_ ft. To \_\_\_\_\_ ft.  
Size \_\_\_\_\_ From \_\_\_\_\_ ft. To \_\_\_\_\_ ft.  
" \_\_\_\_\_ From \_\_\_\_\_ ft. To \_\_\_\_\_ ft.

8. WELL TEST DATA

Static Water Level Below Land Surface 13 ft.  
If Artesian: Flows \_\_\_\_\_ gpm.  
Water Temp. 64 °F Quality good

BAILER TEST  
bailed well dry let set 15 min. well made 45 gal.  
Drawdown \_\_\_\_\_ ft. After Pumping \_\_\_\_\_ hrs. At \_\_\_\_\_ gpm.  
Size of Bailer: 30 gal.



NW 1/4 of NW 1/4 of NW 1/4 of SEC 34 TWP. 22 N RGE. 14 EIM. ~~XXX~~

12. PUMP INFORMATION

Pump Type \_\_\_\_\_  
Power Source \_\_\_\_\_  
Rated Capacity \_\_\_\_\_ gpm.  
Depth of Bowls or Cylinder \_\_\_\_\_ ft.

13. CERTIFICATION

The work described above was done under my supervision, and this report is true and correct to the best of my knowledge.

Name Louis Jennings License # WD265  
Address RR#2 box 96 Claremore, OK. Phone # 918-341-0195  
Signed [Signature] Date 9-27-84

White - Water Resources Board  
Canary - Drillers Copy  
Pink - Drillers Copy

STATE OF OKLAHOMA  
WATER RESOURCES BOARD  
1000 N.E. 10th St. P.O. Box 53585  
Oklahoma City, Oklahoma 73152

Application No. \_\_\_\_\_  
Aquifer \_\_\_\_\_  
Steam System Code \_\_\_\_\_  
Use Code \_\_\_\_\_  
County \_\_\_\_\_  
(Official Use Only)

# 15774

MULTI-PURPOSE WATER WELL REPORT

1. OWNER Otis W. Winchester ADDRESS RR#2 box 815  
Collinsville, Okla. 74021 PHONE 918-371-3059

2. LEGAL DESCRIPTION OF WELL  
NE 1/4 of NE 1/4 of NE 1/4 of sec. 35 : TWP. 22 N Rge. 14 EIM XXXX COUNTY Rogers

3. TYPE OF WORK ☒ New Well ☐ Plugging  
☐ Reconditioning Work ☐ Test

4. PROPOSED / PAST USE ☒ Domestic ☐ Irrigation ☐ Stock  
☐ Municipal ☐ Industrial ☐ Test

5. DRILLING METHOD ☐ Rotary ☐ Rev. Rotary  
☒ Cable ☐ Other \_\_\_\_\_

6. LOG

Material	From	To	Saturated
soil	0	2	
sandy clay	2	6	
sandrock	6	89	X
sandy shale	89	98	
sandrock	98	100	

RECEIVED  
AUG 15 1984  
Oklahoma Water Resources Board

7. NEW WELL CONSTRUCTION DATA

Dates: Started 7/10/84 Completed 7/13/84  
Contractor L & J Jennings Drilling Co.  
Driller Louis Jennings  
Diameter Hole 12 in. Total Depth 100 ft.

CASING RECORD

Diameter From To  
5" PVC 200 in. 1' above ground 20 ft.  
\_\_\_\_\_ in. \_\_\_\_\_ ft. \_\_\_\_\_ ft.

Surface Seal: ☒ Yes ☐ No Type: cement  
Depth of Seal: 20 ft.  
Gravel Packed:  
Gravel Packed From \_\_\_\_\_ ft. to \_\_\_\_\_ ft.  
Amount Used: \_\_\_\_\_

PERFORATION RECORD


Type \_\_\_\_\_ From \_\_\_\_\_ ft. To \_\_\_\_\_ ft.  
Size \_\_\_\_\_ From \_\_\_\_\_ ft. To \_\_\_\_\_ ft.  
" \_\_\_\_\_ From \_\_\_\_\_ ft. To \_\_\_\_\_ ft.

8. WELL TEST DATA

Static Water Level Below Land Surface 17 ft.  
If Artesian: Flows \_\_\_\_\_ gpm.  
Water Temp. 68 °F Quality good

BAILER TEST

Bailed dry 1st set for 1 hr. well made 120 gal.  
Drawdown \_\_\_\_\_ ft. After Pumping \_\_\_\_\_ hrs. At \_\_\_\_\_ gpm.  
Size of Bailer: \_\_\_\_\_ gal.



PUMPING TEST

Drawdown \_\_\_\_\_ ft. After Pumping \_\_\_\_\_ hrs. At \_\_\_\_\_ gpm.

9. PLUGGING DATA

Date Plugged \_\_\_\_\_  
Backfilled With \_\_\_\_\_ Material To \_\_\_\_\_ ft.  
Grouted or Cemented From \_\_\_\_\_ ft. To \_\_\_\_\_ ft.  
Plot Location in Item 11. Show Distances From 2 Section Lines.

NE 1/4 of NE 1/4 of NE 1/4 of SEC 35  
N  
TWP 22 RGE 14 EIM XXXX

10. RECONDITIONING WORK

Date Completed \_\_\_\_\_  
☐ Replaced Casing From \_\_\_\_\_ ft. To \_\_\_\_\_ ft.  
☐ Replaced Screen From \_\_\_\_\_ ft. To \_\_\_\_\_ ft.  
Deepened Well From \_\_\_\_\_ ft. To \_\_\_\_\_ ft.  
Redeveloped Well By \_\_\_\_\_

12. PUMP INFORMATION


Pump Type \_\_\_\_\_  
Power Source \_\_\_\_\_  
Rated Capacity \_\_\_\_\_ gpm.  
Depth of Bowls or Cylinder \_\_\_\_\_ ft.

13. CERTIFICATION

The work described above was done under my supervision, and this report is true and correct to the best of my knowledge.

Name Louis Jennings License # WD265  
Address RR2 box 96 Claremore, Okla. Phone # 918-341-0195  
Signed [Signature] Date 7-15-84

*Reference 11*



## FAX TRANSMITTAL FORM

DATE: 11/10/92

No. of Pages Including Cover: 7

TO: DAVID CROW

MESSAGE:

UNFORTUNATELY, WE DO NOT HAVE MUCH DATA  
IN OUR DATABASE FOR TYLER AND ROGERS COUNTIES.

FROM:

SCOTT CHRISTENSEN

U.S. Geological Survey  
Water Resources Division  
202 N.W. 66th, Bldg. 7  
Oklahoma City, OK 73116

Commercial Number: (405) 231-4256  
FTS: 736-4256

FAX Number: (405) 231-5079  
FTS: 736-5079

DATE: 11/10/92

Preliminary data, subject to revision. U.S. Geological Survey.

PAGE 1

LOCAL WELL NUMBER	OWNER	DEPTH DRILLED (FEET)	DEPTH OF WELL (FEET)	ALTITUDE OF LAND SURFACE (FEET)	WATER LEVEL (FEET)	WATER- LEVEL DATE	AQUIFER CODE	PRIMARY USE OF WATER
21N-14E-10 CBD 1	—	1925	1925	600	—	—	—	—
22N-14E-23 CCB 1	KEPLER BERNICE	—	40.0	620	19.75	06-10-77	323SMNL	U - Unused
22N-14E-26 CBC 1	JONES G W	—	55.0	640	22	07-23-80	110ALVM	—
21N-13E-10 DAA 1	STANLEY F	—	46.0	670	9.15	06-27-77	323SMNL	U
21N-14E-05 AAB 1	GOSVENER ATLAS	—	82.0	655	20.06	06-08-77	323SMNL	I - Irrigation
21N-14E-20 BBC 1	SMITH HAYWARD	—	—	—	—	—	323SMNL	S - Stock
22N-13E-13 ADC 1	MCALANERY KENNETH	—	90.0	—	—	—	323SMNL	H
22N-13E-26 BOC 1	HEINRICH M	—	26.0	—	3.39	06-08-77	323SMNL	U
22N-14E-08 ACD 1	ABEL, DONALD L	—	30.5	635	—	—	—	H - Domestic

323 SMNL = Seminoe Formation

110 ALVM = Alluvium

11/10/92 17:34 008 736 5079

USGS, WRD, URS, UK --- USGS SOLID WASTE

0002

RECORD NUMBER 97704222  
STATION NUMBER 361836095540001  
STATION NAME 21N-13E-10 DAA 1  
DATE OF COLLECTION 06-27-1977 1030 - -

## PARAMETERS INCLUDED IN THIS RECORD ARE—

NO.	CODE	REMARK	VALUE.....	DESCRIPTION.....
1	00010		16.0	WATER TEMPERATURE, DEGREES CELSIUS
2	00095		250	SPECIFIC CONDUCTANCE, US/CM @ 25 DEGREES CENTIGRADE
3	00400		7.4	PH, WATER, WHOLE, FIELD, STANDARD UNITS
4	00940		53	CHLORIDE DISSOLVED (MG/L AS CL)
5	00945		750	SULFATE DISSOLVED (MG/L AS SO4)
6	01046		40	IRON DISSOLVED (UG/L AS FE)

11/10/92

17:35

208 736 5079

USGS, WRD OK, OK --- OSDH SOLID WASTE

0003

RECORD NUMBER 97704223  
 STATION NUMBER 361838095540801  
 STATION NAME 21N-13E-10 DAA 1  
 DATE OF COLLECTION 06-28-1977 1030

PARAMETERS INCLUDED IN THIS RECORD ARE--

NO.	CODE.	REMARK	VALUE.....	DESCRIPTION.....
1	00010		16.0	WATER TEMPERATURE, DEGREES CELSIUS
2	00027		1028	AGENCY COLLECTING SAMPLE (CODE NUMBER)
3	00028		9999	AGENCY ANALYZING SAMPLE (CODE NUMBER)
4	00095		250	SPECIFIC CONDUCTANCE, US/CM @ 25 DEGREES CENTIGRADE
5	00400		7.4	PH, WATER, WHOLE, FIELD, STANDARD UNITS
6	00040		53	CHLORIDE DISSOLVED (MG/L AS CL)
7	00945		750	SULFATE DISSOLVED (MG/L AS SO4)
8	01046		40	IRON DISSOLVED (UG/L AS FE)

RECORD NUMBER — 97704217  
STATION NUMBER — 361727095505001  
STATION NAME — 21N-14E-20 BBC 1  
DATE OF COLLECTION — 06-27-1977 1530 - -

## PARAMETERS INCLUDED IN THIS RECORD ARE—


NO.	CODE.	REMARK	VALUE.....	DESCRIPTION.....
1	00010		28.5	WATER TEMPERATURE, DEGREES CELSIUS
2	00027		1028	AGENCY COLLECTING SAMPLE (CODE NUMBER)
3	00028		9999	AGENCY ANALYZING SAMPLE (CODE NUMBER)
4	00095		585	SPECIFIC CONDUCTANCE, US/CM @ 25 DEGREES CENTIGRADE
5	00400		5.9	PH, WATER, WHOLE, FIELD, STANDARD UNITS
6	00940		65	CHLORIDE DISSOLVED (MG/L AS CL)
7	00945		76	SULFATE DISSOLVED (MG/L AS SO4)
8	01046		60	IRON DISSOLVED (UG/L AS FE)





RECORD NUMBER \_\_\_\_\_ 98004966  
STATION NUMBER \_\_\_\_\_ 362400095503601  
STATION NAME \_\_\_\_\_ 22N-14E-08 ACD 1  
DATE OF COLLECTION — 07-22-1988 1535 - -

## PARAMETERS INCLUDED IN THIS RECORD ARE—

NO.	CODE.	REMARK	VALUE.....	DESCRIPTION.....
1	00010		31.5	WATER TEMPERATURE, DEGREES CELSIUS
2	00095		3460	SPECIFIC CONDUCTANCE, US/CM @ 25 DEGREES CENTIGRADE
3	00400		7.1	PH, WATER, WHOLE, FIELD, STANDARD UNITS
4	00940		280	CHLORIDE DISSOLVED (MG/L AS CL)
5	00945		1200	SULFATE DISSOLVED (MG/L AS SO4)
6	01046		60	IRON DISSOLVED (UG/L AS FE)
7	01056		200	MANGANESE DISSOLVED (UG/L AS MN)



Oklahoma has two systems of intersecting base lines and meridians: one for the Panhandle, and one for the major portion of the state. The division between the two systems is indicated by the dashed line on the state map to the left.



03N-03E-29 BCD 1

The standard method for describing the location of a data collection site by fractional section, section, township, and range, usually referred to as the legal description, is replaced in this report by a local identifier illustrated by this figure. By the legal method, the location of the site indicated by the dot would be described as SE  $\frac{1}{4}$  SW  $\frac{1}{4}$  NW  $\frac{1}{4}$ , Sec. 29, T. 3 N., R. 3 E. The method used in this report changes the order and indicates quarter subdivisions of the sections by letters. A sequence number is added to provide a unique local identifier for each site. By this method, the location of the site is given as 03N-03E-29 BCD 1.

Figure 7.--Explanation of local identifier.

*Reference 12*

Table 1. Selected Population and Housing Characteristics: 1990  
Rogers County, Oklahoma

The population counts set forth herein are subject to possible correction for undercount or overcount. The United States Department of Commerce is considering whether to correct these counts and will publish corrected counts, if any, not later than July 1, 1991.

Total population	55,170	Total housing units	21,455
SEX		OCCUPANCY AND TENURE	
Male	27,231	Occupied housing units	19,866
Female	27,939	Owner occupied	15,764
		Percent owner occupied	79.4
AGE		Renter occupied	4,102
Under 5 years	4,046	Vacant housing units	1,589
5 to 17 years	11,626	For seasonal, recreational, or occasional use	68
18 to 20 years	2,353	Homeowner vacancy rate (percent)	2.5
21 to 24 years	2,316	Rental vacancy rate (percent)	8.9
25 to 44 years	17,099		
45 to 54 years	7,034	Persons per owner-occupied unit	2.79
55 to 59 years	2,810	Persons per renter-occupied unit	2.60
60 to 64 years	2,271	Units with over 1 person per room	561
65 to 74 years	3,349		
75 to 84 years	1,776	UNITS IN STRUCTURE	
85 years and over	490	1-unit, detached	16,401
Median age	33.9	1-unit, attached	196
Under 18 years	15,672	2 to 4 units	678
Percent of total population	28.4	5 to 9 units	331
65 years and over	5,615	10 or more units	390
Percent of total population	10.2	Mobile home, trailer, other	3,459
HOUSEHOLDS BY TYPE		VALUE	
Total households	19,866	Specified owner-occupied units	10,636
Family households (families)	15,928	Less than \$50,000	3,324
Married-couple families	13,861	\$50,000 to \$99,999	6,162
Percent of total households	69.8	\$100,000 to \$149,999	928
Other family, male householder	537	\$150,000 to \$199,999	161
Other family, female householder	1,530	\$200,000 to \$299,999	47
Nonfamily households	3,938	\$300,000 or more	14
Percent of total households	19.8	Median (dollars)	63,700
Householder living alone	3,528	CONTRACT RENT	
Householder 65 years and over	1,536	Specified renter-occupied units paying cash rent	3,525
Persons living in households	54,587	Less than \$250	1,529
Persons per household	2.75	\$250 to \$499	1,807
GROUP QUARTERS		\$500 to \$749	179
Persons living in group quarters	583	\$750 to \$999	9
Institutionalized persons	485	\$1,000 or more	1
Other persons in group quarters	98	Median (dollars)	268
RACE AND HISPANIC ORIGIN		RACE AND HISPANIC ORIGIN OF HOUSEHOLDER	
White	47,242	Occupied housing units	19,866
Black	456	White	17,477
Percent of total population	0.8	Black	163
American Indian, Eskimo, or Aleut	7,117	Percent of occupied units	0.8
Percent of total population	12.9	American Indian, Eskimo, or Aleut	2,137
Asian or Pacific Islander	188	Percent of occupied units	10.8
Percent of total population	0.3	Asian or Pacific Islander	42
Other race	167	Percent of occupied units	0.2
Hispanic origin (of any race)	618	Other race	47
Percent of total population	1.1	Hispanic origin (of any race)	155
		Percent of occupied units	0.8

The user should note that there are limitations to many of these data. Please refer to the technical documentation provided with Summary Tape File 1A for a further explanation on the limitations of the data.

Table 1. Selected Population and Housing Characteristics: 1990  
Tulsa County, Oklahoma

The population counts set forth herein are subject to possible correction for undercount or overcount. The United States Department of Commerce is considering whether to correct these counts and will publish corrected counts, if any, not later than July 1, 1991.

Total population	503,341	Total housing units	227,834
SEX		OCCUPANCY AND TENURE	
Male	242,405	Occupied housing units	202,537
Female	260,936	Owner occupied	122,944
		Percent owner occupied	60.7
AGE		Renter occupied	79,593
Under 5 years	38,835	Vacant housing units	25,297
5 to 17 years	92,659	For seasonal, recreational, or occasional use	450
18 to 20 years	21,926	Homeowner vacancy rate (percent)	4.0
21 to 24 years	28,768	Rental vacancy rate (percent)	12.4
25 to 44 years	170,157		
45 to 54 years	50,597	Persons per owner-occupied unit	2.59
55 to 59 years	21,580	Persons per renter-occupied unit	2.19
60 to 64 years	20,592	Units with over 1 person per room	5,512
65 to 74 years	33,970		
75 to 84 years	18,243	UNITS IN STRUCTURE	
85 years and over	6,014	1-unit, detached	148,654
Median age	32.7	1-unit, attached	7,721
Under 18 years	131,494	2 to 4 units	13,743
Percent of total population	26.1	5 to 9 units	12,863
65 years and over	58,227	10 or more units	35,370
Percent of total population	11.6	Mobile home, trailer, other	9,483
HOUSEHOLDS BY TYPE		VALUE	
Total households	202,537	Specified owner-occupied units	108,819
Family households (families)	135,243	Less than \$50,000	37,803
Married-couple families	107,430	\$50,000 to \$99,999	54,022
Percent of total households	53.0	\$100,000 to \$149,999	9,717
Other family, male householder	5,439	\$150,000 to \$199,999	3,507
Other family, female householder	22,374	\$200,000 to \$299,999	2,318
Nonfamily households	67,294	\$300,000 or more	1,452
Percent of total households	33.2	Median (dollars)	60,700
Householder living alone	58,318		
Householder 65 years and over	18,463	CONTRACT RENT	
Persons living in households	492,508	Specified renter-occupied units paying cash rent	75,793
Persons per household	2.43	Less than \$250	24,938
GROUP QUARTERS		\$250 to \$499	44,074
Persons living in group quarters	10,833	\$500 to \$749	5,222
Institutionalized persons	5,399	\$750 to \$999	936
Other persons in group quarters	5,434	\$1,000 or more	623
		Median (dollars)	296
RACE AND HISPANIC ORIGIN		RACE AND HISPANIC ORIGIN OF HOUSEHOLDER	
White	417,737	Occupied housing units	202,537
Black	49,618	White	172,821
Percent of total population	9.9	Black	17,875
American Indian, Eskimo, or Aleut	25,401	Percent of occupied units	8.8
Percent of total population	5.0	American Indian, Eskimo, or Aleut	8,609
Asian or Pacific Islander	5,976	Percent of occupied units	4.3
Percent of total population	1.2	Asian or Pacific Islander	1,794
Other race	4,609	Percent of occupied units	0.9
Hispanic origin (of any race)	11,958	Other race	1,438
Percent of total population	2.4	Hispanic origin (of any race)	3,705
		Percent of occupied units	1.8

The user should note that there are limitations to many of these data. Please refer to the technical documentation provided with Summary Tape File 1A for a further explanation on the limitations of the data.

*Reference 13*

## MEMORANDUM

**November 4, 1992**

**To:** Acme Brick PA file

**From:** David S. Crow, OSDH Environmental Specialist *D.S.C.*

This memorandum is to serve as reference for the attached material used in determining the public water supply for the City of Collinsville. The source used is the 1988 Public Water Supply Report.

# PUBLIC WATER SUPPLY REPORT

FACILITY: WASHINGTON CO RWD #3(OLD,#2)  
 OPERATOR: WASHINGTON CO RWD#3 (OLD,#2)  
 ADDRESS : PO BOX 70  
 COLLINSVILLE OK 74021  
 PHONE : 918 3712055

MSIS-NUMBER : 1021406  
 COUNTY : TULSA  
 POPULATION SERVED: 5100

## SYSTEMS SERVED:

3007219 SLEEPY VALLEY MHP #2

3007222 COLLINSVILLE MHP

## SOURCE OF WATER:

COLLINSVILLE LK

## LEGAL DESCRIPTION

S T R M

STORAGE CAPACITY : 1160000 GALLONS  
 AVERAGE PRODUCTION: 1000000 GALLONS/DAY

PRODUCTION CAPACITY: 1400000 GALLONS/DAY

PARAMETERS	UNITS	1988	1986	1985	1984
HARDNESS,CALCIUM	MG/L		114.6	126.0	
CHLORIDE	MG/L	16	17	19	27
FLUORIDE TOTAL	MG/L	0.17	0.10	0.25	0.19
NITRITE-NITRATE AS N	MG/L	< 0.5	< 0.5	< 0.50	< 0.5
PH (LAB)	STD UNIT		7.30	7.50	7.40
SPECIFIC CONDUCTANCE	UMHOS/CM	326			
SULFATE	MG/L		100	52	89
SOLIDS-TOTAL DISS	MG/L		234	208	282
ALKALINITY-TOTAL	MG/L		89.0	163.0	78
HARDNESS-TOTAL	MG/L		189	173	218
TURBIDITY	NTU	2.0	< 1.00	1.00	1
WATER TEMPERATURE	DEG CELS		11.0		
ARSENIC-TOTAL	UG/L	< 15	< 10	< 10	< 10
BARIUM-TOTAL	UG/L	< 45	< 200	< 53	< 210
CADMIUM-TOTAL	UG/L	< 2	< 2	< 2	< 2
CHROMIUM-TOTAL	UG/L	< 10	< 10	< 10	< 10
COPPER-TOTAL	UG/L	< 4	< 4	< 4	< 26
IRON-TOTAL	UG/L	< 100	< 100	< 10	< 100
LEAD-TOTAL	UG/L	< 20	< 20	< 20	< 20
MANGANESE-TOTAL	UG/L	< 20	< 20	< 13	< 20.0
MERCURY-TOTAL	UG/L	< 0.5	< 0.5	< 0.5	< 0.5
SELENIUM-TOTAL	UG/L	< 5	< 5	< 5	< 5
SILVER-TOTAL	UG/L	< 3	< 3	< 7	< 3.0
SODIUM-TOTAL	MG/L	< 10	< 13	< 10	< 19.00
ZINC-TOTAL	UG/L		< 4	< 9	< 14
CORROSIVITY	(CALC)		0.83	0.13	
2,4-D IN WATER	UG/L				< 20.000
SILVEX 2,4,5 TP WTP	UG/L				< 2.000
LINDANE IN WATER	UG/L				< 0.02
ENDRIN IN WATER	UG/L				< 0.03
METHOXYCHLOR IN WTR	UG/L				< 0.07
TOXAPHENE IN WATER	UG/L				< 0.300



## PUBLIC WATER SUPPLY REPORT

FACILITY: WASHINGTON CO RWD #3 (NEW,#1)  
 OPERATOR: WASHINGTON CO RWD #3 (NEW,#1)  
 ADDRESS : PO BOX 70  
 COLLINSVILLE OK 74021

MSIS-NUMBER : 1021418  
 COUNTY : TULSA  
 POPULATION SERVED: 2500

PHONE : 918 3712055

SYSTEMS SERVED:  
 3007228 COLLINSVILLE MHP

## SOURCE OF WATER:

OOLAGAH LAKE  
 RECIRC POND

## LEGAL DESCRIPTION

S T R M  
 S T R M

STORAGE CAPACITY : 1200000 GALLONS  
 AVERAGE PRODUCTION: 500000 GALLONS/DAY

PRODUCTION CAPACITY: 2000000 GALLONS/DAY


PARAMETERS	UNITS	1988	1986	1985
HARDNESS, CALCIUM	MG/L		100.0	118.0
CHLORIDE	MG/L	21	23	19
FLUORIDE TOTAL	MG/L	0.20	0.24	0.24
NITRITE-NITRATE AS N	MG/L	< 0.5	< 0.5	< 0.50
PH (LAB)	STD UNIT		7.20	7.40
SPECIFIC CONDUCTANCE	UMHOS/CM	345		
SULFATE	MG/L		72	46
SOLIDS, TOTAL DISS	MG/L		269	198
ALKALINITY, TOTAL	MG/L		107.0	166.0
HARDNESS, TOTAL	MG/L		186	173
TURBIDITY	NTU	2.0	1.00	1.00
ARSENIC-TOTAL	UG/L	< 15	< 10	< 10
BARIUM TOTAL	UG/L	< 38	< 200	< 62
CADMIUM-TOTAL	UG/L	< 2	< 2	< 2
CHROMIUM-TOTAL	UG/L	< 10	< 10	< 10
COPPER-TOTAL	UG/L		< 6	< 4
IRON-TOTAL	UG/L		23	10
LEAD-TOTAL	UG/L	< 20	< 20	< 20
MANGANESE-TOTAL	UG/L		10	10
MERCURY-TOTAL	UG/L	< 0.5	< 0.5	< 0.5
SELENIUM-TOTAL	UG/L	< 5	< 5	< 5
SILVER-TOTAL	UG/L	< 3	< 3	< 11
SODIUM-TOTAL	MG/L	11	12	10
ZINC-TOTAL	UG/L		24	10
CORROSIVITY (CALC)			0.73	0.23
2,4-D IN WATER	UG/L		< 20	
SILVEX 2,4,5 TP WTR	UG/L		< 2.000	
LINDANE IN WATER	UG/L		< 0.02	
ENDRIN IN WATER	UG/L		< 0.03	
METHOXYCHLOR IN WTR	UG/L		< 0.07	
TOXAPHENE IN WATER	UG/L		< 0.30	

*Reference 14*

Crow

RECEIVED  
OCT 28 1992  
Solid Waste Service


RURAL WATER DISTRICT NO. 3  
WASHINGTON COUNTY, OKLAHOMA  
COLLINSVILLE, OKLAHOMA



*Reference 15*

856 IV NW  
VERA

UNITED STATES  
DEPARTMENT OF THE INTERIOR  
GEOLOGICAL SURVEY



*Reference 16*

**RECORD OF COMMUNICATION**

Date: October 12, 1992  
To: Acme Brick Strip Mine PA file  
From: David S. Crow, OSDH Environmental Specialist *D.S.C.*  
Subject: Surface water intakes within 15 miles of probable point of entry (PPE).

On Monday October 12, 1992, at about 2:00 p.m., I spoke to Gene Dousett of the Oklahoma Water Resources Board, Stream Water Division concerning surface water intakes within 15-miles downstream of the PPE. According to Gene there are no surface water intakes used for domestic drinking water use or irrigation purposes within the 15-mile target distance. The nearest drinking water intake is located in the W2 SEC 3 T21N R15E, approximately 19 miles downstream from the PPE. This intake has three (3) users. The nearest irrigation intake is located in the E2 SEC 10 T21N R15E, approximately 20 miles downstream from the PPE.

*Reference 17*



● CH 2445-06

---


# **Uncontrolled Hazardous Waste Site Ranking System**

## **A Users Manual** (HW-10)

Originally Published in  
the July 16, 1982, *Federal Register*

United States  
Environmental Protection  
Agency

1984



Source: Climatic Atlas of the United States, U.S. Department of Commerce, National Climatic Center, Asheville, N.C., 1979.

**FIGURE 5**  
**NORMAL ANNUAL TOTAL PRECIPITATION (INCHES)**

*Reference 18*

**Joan K. Leavitt, M.D.**  
Commissioner

**OKLAHOMA STATE  
DEPARTMENT OF HEALTH**

**Board of Health**

John B. Carmichael, D.D.S.  
President  
Ernest D. Martin, R.Ph.  
Vice President  
Burdge F. Green, M.D.  
Secretary-Treasurer

Gordon H. Deckert, M.D.  
Dan H. Fieker, D.O.  
Linda M. Johnson, M.D.  
Walter Scott Mason, III  
Lee W. Paden

**1000 NE TENTH  
OKLAHOMA CITY, OK  
73117-1299**

AN EQUAL OPPORTUNITY EMPLOYER



October 1, 1992

Ken Morris  
Planning Division  
Oklahoma Water Resources Board  
6000 N. Harvey  
P.O. Box 150  
Oklahoma City, OK 73101-150

Dear Mr. Morris:

The purpose of this letter is to request information regarding the flood potential of each site listed in the following page. The information provided by your office will be used to describe the flood potential of each site in the preliminary assessments conducted by the OSDH, as authorized by a cooperative agreement with the U.S. Environmental Protection Agency.

For each site, please state the "flood-plain frequency" in years. In addition, attach any of the references used to determine the flood potential.

If you have any questions or comments, please do not hesitate to call me at 271-7099, or Richard Brooks at 271-7049.

Sincerely,

A handwritten signature in black ink, appearing to read "David S. Crow".

David S. Crow  
Environmental Specialist

Attachment

**Acme Brick Strip Mines:** Collinsville, Tulsa Co.  
NE4 SE4 NE4 Sec 31 and SW4 NW4 Sec 32 T22N R14E

**American Smelting & Refining Co.:** Sand Springs, Tulsa Co.  
SW4 SW4 Sec11 and SE4 SE4 Sec10 T19N R11E

**Bailey-Mulkey Post Co.:** Broken Bow, McCurtain Co.  
SE4 SW4 Sec12 T6N R25E

**Eighty-Niner Plaza Dry Cleaners:** Moore, Cleveland Co.  
NW4 NW4 NE4 Sec 4 T10N R3W

**El Reno Gas and Electric:** El Reno, Canadian Co.  
SW4 NE4 Sec 9 T12N R7W

**Limestone Quarry Dump:** Pryor, Mayes Co.  
SW4 SW4 SW4 Sec 31 T21N R20E

**Long, John Smelters & Refiners:** Muskogee, Muskogee Co.  
SE4 Sec 34 T15N R18E

**M & M Drum Co.:** Oklahoma City, Oklahoma Co.  
NE4 Sec 4 T11N R3W

**Muskogee Brick:** Muskogee, Muskogee Co.  
SE4 NE4 Sec 23 and NW4 Sec 24 T15N R18E

**Oklahoma Stoddard & Solvent:** Hennepin, Garvin Co.  
NE4 SE4 SE4 Sec 36 T2N R2W

**Old M & M Drum Co.:** Oklahoma City, Oklahoma Co.  
SE4 Sec 32 T12N R3W

**Petroleum Electronics Mfg., Inc.:** Tulsa, Tulsa Co.  
SE4 SE4 Sec 4 T19N R12E

**Power Electronics Mfg., Inc.:** Tulsa, Tulsa Co.  
SE4 SE4 Sec 4 T19N R12E

**Precision Chrome Co.:** Tulsa, Tulsa Co.  
SW4 Sec 32 T20N R13E

**Rebel Tanks:** Chickasha, Grady Co. Hwy 81 (east of Delta Faucet)  
NE4 NE4 SW4 Sec 20 T7N R7W

**Swan Hose Dump:** Stillwater, Payne Co.  
SE4 SW4 Sec 20 T20N R2E

**Ted Smith Property:** Oklahoma City, Oklahoma 2317 South Eastern  
SE4 Sec 11 T11N R3W

**U.S. Navy Dump Grounds:** Norman, Cleveland Co.  
SW4 SW4 Sec 8 T8N R2W

**NATIONAL FLOOD INSURANCE PROGRAM**

**FIRM**  
**FLOOD INSURANCE RATE MAP**

**CITY OF**  
**COLLINSVILLE,**  
**OKLAHOMA**  
**TULSA AND ROGERS COUNTIES**

**PANEL 4 OF 4**

(SEE MAP INDEX FOR PANELS NOT PRINTED)


**COMMUNITY-PANEL NUMBER**  
**400360 0004 A**

**EFFECTIVE DATE:**  
**JULY 2, 1981**



**federal emergency management agency**  
**federal insurance administration**

**RECEIVED**  
OCT 14 1982  
Solid Waste Service



BLACK JACK

DIFFERENT  
SCALE  
THAN  
TULSA CO.

ZONE B  
ZONE C

ZONE B

ZONE B

ZONE C

ZONE C

ZONE B

ZONE B

CORPORATE LIMITS

126TH

RM9

**NATIONAL FLOOD INSURANCE PROGRAM**

**FIRM**  
**FLOOD INSURANCE RATE MAP**

**TULSA COUNTY,  
OKLAHOMA**  
**(UNINCORPORATED AREAS)**


**PANEL 35 OF 255**  
**(SEE MAP INDEX FOR PANELS NOT PRINTED)**

**COMMUNITY-PANEL NUMBER**  
**400462 0035 B**


**EFFECTIVE DATE:**  
**SEPTEMBER 16, 1982**



**Federal Emergency Management Agency**








500-Year Flood Boundary \_\_\_\_\_

100-Year Flood Boundary \_\_\_\_\_

Zone Designations\* 

100-Year Flood Boundary \_\_\_\_\_

500-Year Flood Boundary \_\_\_\_\_

Base Flood Elevation Line  
With Elevation In Feet\*\* 513

Base Flood Elevation in Feet (EL 987)

Where Uniform Within Zone\*\*

Elevation Reference Mark RM7X

Zone D Boundary \_\_\_\_\_

River Mile M1.5

\*\* Referenced to the National Geodetic Vertical Datum of 1929

### \*EXPLANATION OF ZONE DESIGNATIONS

ZONE	EXPLANATION
A	Areas of 100-year flood; base flood elevations and flood hazard factors not determined.
A0	Areas of 100-year shallow flooding where depths are between one (1) and three (3) feet; average depths of inundation are shown, but no flood hazard factors are determined.
AH	Areas of 100-year shallow flooding where depths are between one (1) and three (3) feet; base flood elevations are shown, but no flood hazard factors are determined.
A1-A30	Areas of 100-year flood; base flood elevations and flood hazard factors determined.
A99	Areas of 100-year flood to be protected by flood protection system under construction; base flood elevations and flood hazard factors not determined.
B	Areas between limits of the 100-year flood and 500-year flood; or certain areas subject to 100-year flooding with average depths less than one (1) foot or where the contributing drainage area is less than one square mile; or areas protected by levees from the base flood. (Medium shading)
C	Areas of minimal flooding. (No shading)
D	Areas of undetermined, but possible, flood hazards.
V	Areas of 100-year coastal flood with velocity (wave action); base flood elevations and flood hazard factors not determined.
V1-V30	Areas of 100-year coastal flood with velocity (wave action); base flood elevations and flood hazard factors determined.

### NOTES TO USER

Certain areas not in the special flood hazard areas (zones A and V) may be protected by flood control structures.

This map is for use in administering the National Flood Insurance Program; it does not necessarily identify all areas subject to flooding, particularly from local drainage sources of small size, or all planimetric features outside special flood hazard areas. The coastal flooding elevations shown may differ significantly from those developed by the National Weather Service for hurricane evacuation planning.

For adjoining map panels, see separately printed Index To Map Panels.

INITIAL IDENTIFICATION:

AUGUST 23, 1974

FLOOD HAZARD BOUNDARY MAP REVISIONS:

MAY 17, 1977

*Reference 19*



Endangered and Threatened  
Species of Texas  
and Oklahoma  
1987

WILDLIFE 88:8 (1987)



E

Texas	Bald eagle	Endangered
	Interior least tern	Endangered
	Whooping crane	Endangered
	Peregrine falcon	Endangered
	Arkansas River shiner	Category 1 Candidate
	Arkansas River speckled chub	Category 2 Candidate
	Texas horned lizard	Category 2 Candidate
	White-faced ibis	Category 2 Candidate
	Ferruginous hawk	Category 2 Candidate
	Long-billed curlew	Category 2 Candidate
	Western Snowy plover	Category 2 Candidate
	Mountain plover	Category 2 Candidate
	Swift fox	Category 2 Candidate
Tillman	Interior least tern	Endangered
	Whooping crane	Endangered
	Texas horned lizard	Category 2 Candidate
	White-faced ibis	Category 2 Candidate
	Ferruginous hawk	Category 2 Candidate
	Long-billed curlew	Category 2 Candidate
	Western Snowy plover	Category 2 Candidate
	Texas kangaroo rat	Category 2 Candidate
Tulsa	Peregrine falcon	Endangered
	Bald eagle	Endangered
	Interior least tern	Endangered
	Piping plover	Threatened
	Prairie mole cricket	Proposed Threatened
	Paddlefish	Category 2 Candidate
	Arkansas River shiner	Category 1 Candidate
	Arkansas River speckled chub	Category 2 Candidate
	Texas horned lizard	Category 2 Candidate
	White-faced ibis	Category 2 Candidate
	Long-billed curlew	Category 2 Candidate
	Western Snowy plover	Category 2 Candidate
	Migrant loggerhead shrike	Category 2 Candidate
Wagoner	Peregrine falcon	Endangered
	Bald eagle	Endangered
	Interior least tern	Endangered
	Piping plover	Threatened
	Prairie mole cricket	Proposed Threatened
	Ozark spiderwort	
	( <i>Tradescantia ozarkana</i> )	Category 2 Candidate
	Paddlefish	Category 2 Candidate
	Blue sucker	Category 2 Candidate
	Arkansas River shiner	Category 1 Candidate
	Arkansas River speckled chub	Category 2 Candidate
	Alligator snapping turtle	Category 2 Candidate
	Texas horned lizard	Category 2 Candidate
	Migrant loggerhead shrike	Category 2 Candidate
Washington	Peregrine falcon	Endangered
	Bald eagle	Endangered
	Piping plover	Threatened
	Prairie mole cricket	Proposed Threatened
	Ozark chinquapin	Category 1 Candidate
	( <i>Castanea pumila</i> var. <i>ozarkensis</i> )	
	Alligator snapping turtle	Category 2 Candidate
	Texas horned lizard	Category 2 Candidate
	White-faced ibis	Category 2 Candidate
	Ferruginous hawk	Category 2 Candidate
	Long-billed curlew	Category 2 Candidate
	Western Snowy plover	Category 2 Candidate
	Mountain plover	Category 2 Candidate
	Migrant loggerhead shrike	Category 2 Candidate
Washita	Whooping crane	Endangered
	Prairie mole cricket	Proposed Threatened
	Texas horned lizard	Category 2 Candidate
	White-faced ibis	Category 2 Candidate
	Ferruginous hawk	Category 2 Candidate
	Long-billed curlew	Category 2 Candidate
	Western Snowy plover	Category 2 Candidate

Pushmataha	Peregrine falcon	Endangered	
	Piping plover	Threatened	
	Red-cockaded woodpecker	Endangered	
	Leopard darter C/H	Threatened	
	Ouachita Mtns. indigo ( <i>Amorpha ouachitensis</i> )	Category 2 Candidate	
	Cumberland sand grass ( <i>Calamovilfa arcuata</i> )	Category 2 Candidate	
	Small-headed pipewort ( <i>Eriocaulon kornickianum</i> )	Category 2 Candidate	
	Ouachita rock pocketbook	Category 1 Candidate	
	Three-toothed long-horned caddisfly	Category 2 Candidate	
	Scaleshell mussel	Category 2 Candidate	
	Ouachita Mountain shiner	Category 2 Candidate	
	Alligator snapping turtle	Category 2 Candidate	
	Migrant loggerhead shrike	Category 2 Candidate	
	Roger Mills	Interior least tern	Endangered
Whooping crane		Endangered	
Bald eagle		Endangered	
Arkansas River shiner		Category 1 Candidate	
Arkansas River speckled chub		Category 2 Candidate	
Texas horned lizard		Category 2 Candidate	
White-faced ibis		Category 2 Candidate	
Ferruginous hawk		Category 2 Candidate	
Long-billed curlew		Category 2 Candidate	
Western Snowy plover		Category 2 Candidate	
Swift fox		Category 2 Candidate	
Rogers		Peregrine falcon	Endangered
		Bald eagle	Endangered
		Interior least tern	Endangered
	Piping plover	Threatened	
	Prairie mole cricket	Proposed Threatened	
	Ozark chinquapin ( <i>Castanea pumila</i> var. <i>ozarkensis</i> )	Category 1 Candidate	
	Western prairie fringed orchid	Threatened	
	Arkansas darter	Category 2 Candidate	
	Texas horned lizard	Category 2 Candidate	
	Alligator snapping turtle	Category 2 Candidate	
	White-faced ibis	Category 2 Candidate	
	Ferruginous hawk	Category 2 Candidate	
	Long-billed curlew	Category 2 Candidate	
	Western Snowy plover	Category 2 Candidate	
	Migrant loggerhead shrike	Category 2 Candidate	
	Seminole	Peregrine falcon	Endangered
		Interior least tern	Endangered
		Piping plover	Threatened
Arkansas River shiner		Category 1 Candidate	
Arkansas River speckled chub		Category 2 Candidate	
Texas horned lizard		Category 2 Candidate	
Migrant loggerhead shrike		Category 2 Candidate	
Sequoyah	Peregrine falcon	Endangered	
	Bald eagle	Endangered	
	Interior least tern	Endangered	
	American burying beetle	Endangered	
	Piping plover	Threatened	
	<i>Carex fissa</i>	Category 2 Candidate	
	Paddlefish	Category 2 Candidate	
	Longnose darter	Category 2 Candidate	
	Arkansas River shiner	Category 1 Candidate	
	Arkansas River speckled chub	Category 2 Candidate	
	Alligator snapping turtle	Category 2 Candidate	
	Migrant loggerhead shrike	Category 2 Candidate	
	Eastern small-footed bat	Category 2 Candidate	
Stephens	Bald eagle	Endangered	
	Whooping crane	Endangered	
	Peregrine falcon	Endangered	
	Texas horned lizard	Category 2 Candidate	
	White-faced ibis	Category 2 Candidate	
	Western Snowy plover	Category 2 Candidate	

*Reference 20*



*Oklahoma*  
*Natural Heritage Inventory*

OKLAHOMA BIOLOGICAL SURVEY  
2001 Priestly Avenue, Building 605  
Norman, Oklahoma 73019-0543, USA  
(405) 325-1985  
FAX: (405) 325-7702

**RECEIVED**

AUG 31 1992

Solid Waste Service

Richard L. Brooks, R.S.  
Senior Environmental Specialist  
Oklahoma Dept. of Health  
1000 NE Tenth  
Oklahoma City, OK 73117-1299

August 27, 1992

Dear Mr. Brooks:

This letter is in response to your request for information on possible endangered species or other elements of biological significance at the following sites:

✓S/2 NE4 Sec 31 & S/2 NW/4 Sec 32 T22N R14E of IM, Tulsa County  
SE/4 SE/4 Sec 36 T2N R2W of IM, Garvin County  
NW/4 SW/4 T20N R13E of IM, Tulsa County  
SE/4 SW/4 Sec 20 T20N R2E of IM, Payne County  
SW/4 NW/4 Sec 31 T14N R2W of IM, Oklahoma County

The Oklahoma Natural Heritage Inventory maintains a database on the status and location of rare species and significant ecological communities in Oklahoma. We have reviewed the information currently in the Heritage Inventory database and found no records of on-site elements. However, elements were found within a four mile radius and/or fifteen miles downstream from some sites. These are listed on the attached table.

The Heritage Inventory database is the most current comprehensive one available on the rare biota of Oklahoma. However, such a database is only as complete as the information that has been collected. For this reason, we cannot state for certain whether or not a given site harbors rare species or significant communities. We suggest you also contact the Environmental Division of the Oklahoma Department of Wildlife Conservation and the U.S. Fish and Wildlife Service, as they may have site specific information of which we are unaware.

If you have any questions concerning the information we provided, please call Ian Butler at (405) 325-7599.

Sincerely,

*Ian H. Butler*

for Ian H. Butler  
Data Coordinator

cc: Ron Suttles, Oklahoma Dept. of Wildlife Conservation  
Stephen Forsythe, U.S. Fish and Wildlife Service

IHB.tlb



OKLAHOMA NATURAL HERITAGE INVENTORY  
TABLE OF PROXIMAL ELEMENT OCCURRENCES

REQUESTED BY: Oklahoma Department of Health  
DATE OF REQUEST: August 25, 1992

SITE SPECIES NAME	STATUS		ONHI RANK		LAST SEEN	
	FED	STATE	GLOBAL	STATE		
✓ S/2 NE/4 Sec 31 & S/2 NW/4 Sec 32 T22N R14E of IM						
<u>Gryllotalpa major</u> (Prairie Mole Cricket)	*	C2	SS2	G2	S2	1990
SE/4 SE/4 Sec 36 T2N R2W of IM						
no findings						
NW/4 SW/4 Sec 32 T20N R13E of IM						
<u>Sterna antillarum</u> (Least Tern)	* **	LE	E	G4	S2B	1991
SE/4 SW/4 Sec 20 T20N R2E of IM						
<u>Ulmus-america-</u> <u>celtis spp.</u> (Central Bottomland Forest)	**	none	none	G2G3	S2S3	unknown
<u>Penstemon oklahomensis</u> (Oklahoma Beardtongue)	* **	none	none	G3	S3	1977

-----  
\* Occurrence within a four mile radius from the site.  
\*\* Occurrence within fifteen miles downstream from the site.

Please note that the information request for SE/4 SE/4 T19N R12E of IM, Tulsa County will be sent at a later date as that topo map is out of the office.

**OKLAHOMA NATURAL HERITAGE INVENTORY**  
**EXPLANATION OF NATURAL HERITAGE RARITY RANKINGS**

Each species and natural community is given two ranks, a global (G) rank reflecting its rarity throughout the world, and, a state (S) rank reflecting its rarity within Oklahoma.

Global Rank

- G1 Critically imperiled globally because of extreme rarity (5 or fewer occurrences or very few remaining individuals or acres) or because of some factor of its biology making it especially vulnerable to extinction.
- G2 Imperiled globally because of rarity (6 to 20 occurrences or few remaining individuals or acres) or because of other factors demonstrably making it very vulnerable to extinction throughout its range.
- G3 Either very rare and local throughout its range, or found locally (even abundantly at some of its locations) in a restricted range, or because of other factors making it vulnerable to extinction throughout its range; in the range of 21 to 100 occurrences.
- G4 Apparently secure globally, though it may be quite rare in parts of its range, especially at the periphery.
- G5 Demonstrably secure globally, though it may be quite rare in parts of its range, especially at the periphery.
- GH Historically known, with the expectation that it may be rediscovered.
- GX Believed to be extinct.
- GU Not yet ranked.

State Rank

- S1 Critically imperiled in Oklahoma because of extreme rarity (5 or fewer occurrences or very few remaining individuals or acres) or because of some factor of its biology making it especially vulnerable to extinction.
- S2 Imperiled in Oklahoma because of rarity (6 to 20 occurrences or few remaining individuals or acres) or because of other factors demonstrably making it very vulnerable to extinction throughout its range.
- S3 Rare and local in Oklahoma( though it may be abundant at some of its locations); in the range of 21 to 100 occurrences.
- S4 Apparently secure in Oklahoma.
- S5 Demonstrably secure in Oklahoma.
- SH Historically known from Oklahoma, but possibly extirpated; not seen in the last 15 years.
- SR Reported in Oklahoma, but not documented.
- SRF Falsely reported in Oklahoma.
- S#M\* Migratory.
- S#N Nonbreeding in Oklahoma.
- S#B Breeding in Oklahoma
- SU Not yet ranked.
- SX Believed to be extirpated from Oklahoma.

\* Rank number (#) included to indicate status.

Other Rank Symbols

- ? There is a question about the given rank.
- Q There are taxonomic questions concerning a species.
- T Associated with global rank, indicating a global rarity rank for a particular subspecific taxon.

## EXPLANATION OF STATE AND FEDERAL STATUS ABBREVIATIONS

### State (Status determined by the Oklahoma Department of Wildlife Conservation)


- E Endangered in Oklahoma.
- T Threatened in Oklahoma.
- SN State nominated for listing as threatened or endangered.
- SS Species of Special Concern
  - SS1 - a species that current evidence indicates is especially vulnerable to extirpation because of limited range, low population or other factors.
  - SS2 - species identified by technical experts as possibly threatened or vulnerable to extirpation but for which additional information is needed.
- P Protected from hunting by regulation.

### Federal (Status determined by the US Fish and Wildlife Service, Office of Endangered Species)


- LE Listed Endangered.
- PE Proposed for listing as Endangered.
- LT Listed Threatened.
- PT Proposed for listing as Threatened.
- LELT Listed Endangered in some USFWS regions and Threatened in others.
- C1 Category 1 species for listing. Species determined to be in need of protection by listing as Endangered or Threatened.
- C2 Category 2 species for listing. Species needs additional study to determine whether it should be listed as Endangered or Threatened.
- C2\* Category 2 species recommended for elevation to C1 status.
- 3C Category 3 species. Currently, the species is not recommended for listing as Endangered or Threatened.

Additional information about the federal or state status of species may be available directly from, respectively, the US Fish and Wildlife Service, Ecological Services Office, Tulsa, (918) 581-7458, or, from the Oklahoma Department of Wildlife Conservation, Natural Resources Section, Oklahoma City, (405) 521-4616.

Acme Strip Mines



27 T2N R14E  
 Quadname Collinsville.  
 4000  
 1 MILE  
 4000 5000 6000 7000 FEET  
 1 KILOMETER  
 10 FEET  
 DATUM OF 1929



ROAD CLASSIFICATION  
 Heavy-duty ——— Light-duty ———  
 Medium-duty ——— Unimproved ———  
 U. S. Route ——— St. ———

COLLINSVILLE  
 N3615—A

ALL MAP ACCURACY STANDARDS  
 COLORADO 80225 OR RESTON, VIRGINIA 22092  
 SURVEY, NORMAN, OKLAHOMA 73069  
 AND SYMBOLS IS AVAILABLE ON REQUEST

1'  
 PHOTOREDUCTION  
 AMS 6856 IV

6/9/88

6.3.2-5

Allegany.....MDALLE  
Anne Arundel.....MDANNE  
Baltimore.....MDBALT  
Baltimore City....MDBALC  
Calvert.....MDCALV  
Caroline.....MDCARO  
Carroll.....MDCARR  
Cecil.....MDCECI  
Charles.....MDCHAR  
Dorchester.....MDDORC  
Frederick.....MDFRED  
Garrett.....MDGARR

Harford.....MDHARF  
Howard.....MDHOWA  
Kent.....MDKENT  
Montgomery.....MDMONT  
Prince Georges....MDPRIN  
Queen Annes.....MDQUEE  
Saint Marys.....MDSAIN  
Somerset.....MDSOME  
Talbot.....MDTALB  
Washington.....MDWASH  
Wicomico.....MDWICO  
Worcester.....MDWORC

#### QUADCODE (32)

Code for the USGS topographic quadrangle using the Universal Map Code Locator system (UMCLS, see Appendix I). Enter centroid quad first, then any additional quads that the EO covers partly or fully. Multiple quads are separated by a space. Example:

3807754 3807764 3807765

#### QUADNAME (40)

Quad name. List the centroid quad first. Use a comma but no space as a separator. Use the USGS quad names as they appear on the quad.

#### PRECISION (2)

Precision to which EO as described can be located on a topographic map.

These codes are defined as follows:

#### Symbol

○ S = Seconds; accuracy of locality mappable within a three-second radius (roughly the area covered by the dot), i.e., the place as described in source(s) is precisely mappable, whether or not element is known to occur precisely there.

△ M = minute (within a one minute radius, approx. 2 km or 1.5 mi. from centerpoint of your dot.)

□ G = general (to quad or place name precision only, precision within about 8 km or 5 mi.)

U = Unmappable (cannot be mapped due to incomplete or inaccurate information)

[ To indicate whether or not the EO has been found at the site or that it has been extirpated see the EORANK field.

Note also that an M or G report is sometimes kept as a separate EO record despite knowledge of an S report within the same M- or G-precision area on the grounds that confirming the

*Reference 21*

Alt-Z Help |Alt-Tab Menu| EC | | |FDX|CR| | MTEZ by MagicSoft, Inc.  
 Enter the next ring distance  
 TGEMS>

Enter program execution mode: B (batch) or I (interactive)  
 TGEMS> i

Acme Brick Strip Mines

LATITUDE 36:20:45 LONGITUDE 95:50:51 POPULATION

KM	0.00-.400	.400-.810	.810-1.60	1.60-3.20	3.20-4.80	4.80-6.40	SECTOR TOTALS
S 1	0	0	0	3241	0	0	3241
S 2	0	0	1285	0	897	146	2328
S 3	0	0	37	0	0	0	37
S 4	0	0	0	0	3075	0	3075
S 5	0	0	0	0	0	165	165
S 6	0	0	0	0	911	0	911
RING TOTALS	0	0	1322	3241	4883	311	9757

press RETURN to continue

*1990 Census Data*  
*Compiled by R. H. D. Brooks*  
*10/6/92.*